

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22762-00-00
Spot: E2NWSE Sec/Twnshp/Rge: 8-13S-18W
1980 feet from S Section Line, 1650 feet from E Section Line
Lease Name: POLIFKA Well #: 1
County: ELLIS Total Vertical Depth: 3810 feet

Operator License No.: 7064
Op Name: DORZWEILER, LEO R. DBA CATTLEM
Address: 2260 CATHERINE RD.
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3801	0	125 SXS CMT
SURF	8.625	266	0	160 SXS CMT

#12383

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/12/2005 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: LEO DORZWEILER Company: CATTLEMANS OIL OPERATIONS Phone: (785) 625-5394

Proposed Plugging Method: Ordered 300 sxs cement - 26 sxs gel spacer - 500# hulls.

Plugging Proposal Received By: ROGER MOSES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/12/2005 11:30 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

DV Tool at 1500' with 475 sxs cement.
Tied to 5 1/2" casing - spotted 25 sxs cement with 150# hulls, followed with 25 sxs gel.
Squeezed 200 sxs cement with 100# hulls.
Max. P.S.I. 150#. S.I.P. 150#.
Tied to 8 5/8" x 5 1/2" - pressured to Max. P.S.I. 500# - took no cement.
Total of 225 sxs 60/40 pozmix - 10% gel - 25 sxs gel and 250# hulls.

Perfs:

Top	Bot	Thru	Comments
3506	3509		
3494	3496		

Remarks: ALLIED CEMENTING COMPANY. CATTLEMANS OIL-WATER.

Plugged through: CSG

District: 04

HD.

Signed Roger L. Moses
(TECHNICIAN)

INVOICED

DATE 9-21-05
TV NO 2006060457

RECEIVED
Form CP-2/3

SEP 20 2005

KCC WICHITA

SEP 13 2005

INVOICE

REPLACEMENT CARD

CATTLEMANS OIL OPERATIONS
 CATHERINE RT, BOX 32 #1 POLIFKA 8-13-18W
 HAYS, KS 67601 C E/2 NW SE
 CONTR THUNDERSIRD DRLG CTY ELLIS
 GEOL _____ FIELD WC(POL REV)

E 2164 KB CM 12/18/81 ^{CARD} ISSUED 5/13/82 IP P 15 BOPD & WTR
 LKC 3494-3509 OA

+	+	+
+	+	+

API 15-051-22,762

SMP	TOPS	DEPTH	DATUM
ANH		1454	+ 710
TOP		3181	-1017
HEEB		3420	-1256
LANS		3466	-1302
WEA ARE		3752	-1568
ARE		3783	-1619
RTQ		3810	-1646
LOGGED - 4" DIFFERENCE IN MEASUREMENTS			

8-5/8" 266/160sx, 5 1/2" 3801/125sx
 DST (1) 3474-3520(LKC)/45-45-45-45,
 120' HO&GCM, 420' C&GOW, 240' W,
 SIF 1125-1086#, FF 99-357/396-545#
 DST (2) 3515-21(LOWER KC)/50-50-30-30
 1770' SW, SIF 1027-1105#, FF 198-
 673/742-889#
 MIST - CO, PF (LKC) 6/3506-09, 4/3494-
 95, AC 1000G (15% REG), SWB LD W/GSO,
 POP, P 21 BOPD & 70% W (GR 32"), DECL
 TO 15 BOPD & WTR, 5/15/82

INFO RELEASED: 6/10/82
 WAS OIL WELL - TIGHT ROLE

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS