

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-05041-00-00  
Spot: W2SESE Sec/Twnshp/Rge: 27-11S-17W  
660 feet from S Section Line, 990 feet from E Section Line  
Lease Name: BAUMER B Well #: 39  
County: ELLIS Total Vertical Depth: 3569 feet

Operator License No.: 32754  
Op Name: ELYSIUM ENERGY, L.L.C.  
Address: 1625 BROADWAY, SU 2000  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3509	0	200 SX CMT
SURF	8.625	1230	0	525 SX CMT

#115 99

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/08/2005 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: CHRIS GOTTSCHALK Company: ELYSIUM ENERGY, LLC Phone: (785) 625-4052

Proposed Plugging Method: 09/08/2005 - Ordered out 175 sxs 60/40 pozmix - 10% gel - 15 sxs gel spacer.  
09/09/2005 - Ordered out 425 sxs 60/40 pozmix - 10% gel.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/09/2005 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

09/08/2005 - Ran tubing to 3502'. Allied pumped 15 sxs gel spacer, followed with 50 sxs 60/40 pozmix - 10% gel.  
Pulled tubing to 1715' - Allied pumped 125 sxs cement.  
Pulled tubing to 630' - Allied pumped 30 barrels fresh water - never saw cement until returns.  
Will run in and tag cement in the morning.  
09/09/2005 - Tagged TOC at 1209'. Perforated two holes at 1100'.  
Allied pumped 215 sxs 60/40 pozmix - 10% gel down 5 1/2" casing - circulated cement out 8 5/8".  
Displaced cement to 630' - shut in.  
Note: Oil well plugged from 650' to RTD. Converting to WSW.

Perfs:

Top	Bot	Thru	Comments
3509	3569	OH	

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

*Richard Williams*

(TECHNICIAN)

INVOICED

DATE 9-21-05  
INV. NO. 2006060459

RECEIVED

SEP 20 2005

KCC WICHITA

Form CP-2/3

SEP 13 2005

DEEP ROCK OIL CORP

#39 BAUMER

27-11-17W  
W2 SE SE

Contr. \_\_\_\_\_ ELLIS County

E. 2014 Comm. 2-24-47 Comp. 4-25-47 IP 104 EOPD

Tops	Depth	Datum	Casing
ANH	1217		8" 1230
			5" 3507
HEEB	3233		
			Swb 11 BO/12 hrs
LANS	3256		A/500
			Swb 18 BO/12 hrs
SIMP	3496		
ARB	3507		
TD	3518		


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS