

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21765-00-00
Spot: SESENE Sec/Twnshp/Rge: 18-9S-23W
2310 feet from N Section Line, 330 feet from E Section Line
Lease Name: KLENK Well #: 9
County: GRAHAM Total Vertical Depth: 3940 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3938	0	150 SX CMT
SURF	8.625	206	0	160 SX CMT

\$ 125⁰⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/30/2005 11:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 500#hulls - 13 sxs gel.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/30/2005 12:30 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

4 1/2" production casing set at 3938' w/150 sxs cement.
8 5/8" surface casing set at 206' w/160 sxs cement.
Rigged up cementers and squeezed 25 sxs cement with 200# hulls,
followed with 13 sxs gel and 125 sxs cement with 200# hulls.
Max. P.S.I. 400#. S.I.P. 200#.
8 5/8" - pressured up 500#. No cement pumped.

Perfs:

Top	Bot	Thru	Comments
3892	3900		
3856	3862		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

Dennis L. Hamel

(TECHNICIAN)

INVOICED

DATE

9-21-05

INV. NO

2006060460

RECEIVED

SEP 20 2005

KCC WICHITA

Form CP-2/3

AUG 30 2005

JOHN O. FARMER, INC.

P.O. BOX 352

#9 KLENK

18-9-23W

SE SE NE


RUSSELL, KS 67665

CONTR COMPANY TOOLS

CTY GRAHAM

GEOL

FIELD ERNST NW



ELV 2378 KB SPD 3/15/83

CARD ISSUED 6/2/83

IP P 83' BOPD

API 15-065-21,765

LANS 3856-3900 OA

SMP	Tops	Depth/Datum
ANH	1996+ 382
B/ ANH	2031+ 347
HEEB	3663-1285
TOR	3688-1310
LANS	3706-1328
RTD	3940-1562

8 5/8 " 206/160SX; 4 1/2 " 3938/150SX

DST (1) 3845-70 (LANS) / 45-45-45-45, 1860' GIP, REC 150' OCM, 140' FO, SIP 204-204#, FP 61-102 / 102-122#

DST (2) 3879-3904 (LANS) / 45-45-45-45, 270' GIP, REC 90' OCM, 180' HOCM, SIP 817-817#, FP 81-102 / 122-132#

MICT - CO, PF (LANS) 3892-3900 & 3856-62 W/4 SPF, AC 2000G, SWB LD, T&R, POP, P 83 BOPD, 5/1/83

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

INDEXED