

6 030832

API NUMBER 15- NA

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NESESE SEC. 22, T. 7 S, R. 17 (W/2)

990 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767
Operator: RITCHIE Exp. Inc.
Name & Address: 125 N. MARKET #1000
WICHITA, KANSAS 67202

Lease Name SIMONS Well # 1
County ROOKS 103.68
Well Total Depth 3190 feet
Conductor Pipe: Size 13 3/8" feet 56'
Surface Casing: Size 8 3/8" feet 1074'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor KHELSO CASING PULLING License Number 6050
Address CHASE KANSAS

Company to plug at: Hour: PM Day: 18 Month: 12 Year: 19 86

Plugging proposal received from MILLARD KHELSO.

(company name) KHELSO CASING (phone) _____

logs: 13 3/8 SET @ 56' CWC 8 3/8 SET @ 1074' w/ 600 SX. CWC 4 1/2 SET @ 2966' w/ 175'

PBTD 3170 PERF. 2835-38' 2603-10' ORDER SAND & COM. CMT. 5 SHOTS
& Pull PIPE. ORDER 180 SX. ATH 65/35002 10% GEL 3% ACC 5 SX. HULLS ALLIED
CMT. CO. K&R WATER TRUCKS

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 3:30 PM Day: 18 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND ON PBTD @ 3170 TO 50' ABOVE TOP PERF @ 2550'
AND SPOT 4 SX. COM. CMT. ON SAND WITH BAILER. 3 SHOTS RECOVERED 199 3' OF 4 1/2"
MIX & Pump Down 8 3/8 (10bb) CMT slurry = 20 SX. CMT MIX) Follow w/ 5 SX. HULLS
MIXED IN WITH CMT. SLURRY - USED TOTAL OF 130 SX. CMT. MIX 5 SX. HULLS
MAX. PSI 1800# LOCKED UP. RELEASED PSI BACK TO 600# & CLOSED IN.
Plug COMPLETE

Remarks: (If additional description is necessary, use BACK of this form)

INVOICED observe this plugging.

DATE 1-2-87

INV. NO. 15710

Signed Carl Goodrow (TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas