

3-29

323

6 041292

API NUMBER 15- 163-21,551 -00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SW NW, SEC. 21, T 7, S, R 17 W/EX

2970 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050 W.J. Inc.

Lease Name Bittel Well # 1

Operator: Kelso Casing Pullers & WJ Inc County Rooks

Well Total Depth 3490 feet

Name & Address Box 347

Conductor Pipe: Size 13 3/8 feet 128 w/215 sks

Chase, Ks. 67524

Surface Casing: Size 8 5/8 feet 1198 w/275 sks

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number 113.42

Address Russell, Ks.

Company to plug at: Hour: 8:00 Day: 29 Month: Mar Year: 19 91

Plugging proposal received from Millard Kelso

(company name) Kelso Casing (phone)

were: 4 1/2 casing set at 3416 w/100 sks cement: perfs at 2720 to 3179;

Ordered 100 sks common; plus Ordered 725 sks 65/35 poz 8% gel w/4

1b f.c. plus 6 sks hulls.

RECEIVED
STATE CORPORATION COMMISSION

APR 22 1991

4-22-91

CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 6:30PM Day: 29 Month: Mar Year: 19 91

ACTUAL PLUGGING REPORT Plug bottom w/sand to 2670 and 4 sks cement on sand:

Shot casing at 2500 and 2287 and pulled same: Plug through casing:

Spot 200 sks cement w/400 lbs. hulls at 1866: Pulled up to 1273 and

spotted 100 sks common cement; pulled up to 685 and spotted 100 sks

cement: pulled up to 480 spotted 125 sks cement. (no circ) Ordered add

cement w/200 lbs. hulls at 480. Cement did not circ to surf: Pulled 480 of

add casing; top of cement at 65. Hooked up to 8 5/8 s.p. and pumped add

Remarks: 200 sks of cement; Max 300 lbs. S.I. 100 lbs.

(If additional description is necessary, use BACK of this form.)

INVOICED

(old) ~~xxxxxx~~ observe this plugging.

DATE 4-29-91

Signed Dennis L. Hamel
(TECHNICIAN)

Dennis Hamel

INV. NO. 31700

SEP 27 1991

FORM CP-2/3
Rev. 01-84

3-29