

4-29
4-041575

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-21,430 ⁰⁰⁻⁰⁰

SE SW SW /4 SEC. 20 , 07 S, 17 W
330 feet from S section line
4290 feet from E section line

Operator license# 4619 Lease Kriley well # D-4

Operator: Black Eagle Res/Carl Barnes County Rooks

Address: P.O. Box 515 Well total depth 3276 feet ^{106.47}
Stockton, Kansas 67665 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 1182 feet
w/450 sxs.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing - D.S. & W. Casing License#

Address: Russell, Kansas - Claflin Kansas

Company to plug at: Hour: P.M. Day: 29 Month: April Year: 94

Plugging proposal received from: Carl Barnes

Company: Black Eagle Resources Phone:

Were: 5 1/2" casing set @ 3250' w/150 sxs. cement. O.H. @ 3250' -
3276'. Anhy. @ 1171. Recovered 1886' of 5 1/2" casing.
Ordered 350 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 4:00P.M., Day: 29, Month: April, Year: 94

Actual plugging report: Spot thru casing at 1260'. 175 sxs. 60/40
pozmix - 10% gel with 500# hulls. Pulled casing to 600'. Spot 50 sxs.
to circulate cement at surface. Pulled casing and squeezed 16 sxs.
cement. Max. 500# S.I.P.

Sanded back to 3200' and spotted 5 sxs cement with dump

STATE RECEIVED
CONSERVATION COMMISSION
MAY 05 1994
CONSERVATION DIVISION
WICHITA, KANSAS
5-5-94

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did X observe the plugging.

Dennis L. Hamel

(agent)

INVOICED
DATE MAY 05 1994
INV. NO. 40385