

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-20655-00-00
Spot: SENE Sec/Twnshp/Rge: 9-23S-22W
1980 feet from N Section Line, 660 feet from E Section Line
Lease Name: HOUSMAN Well #: 3
County: HODGEMAN Total Vertical Depth: 4473 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4100		WITH 4 SX CMT
PROD	5.5	4469	0	WITH 75 SX CMT
SURF	8.625	373		WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/02/2005 3:15 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: KIM Company: AMERICAN WARRIOR Phone: (620) 275-7461

Proposed Plugging Method: CIBP @ 4100' WITH 4 SX CMT. RUN TUBING WITH PACKER TO 1400'. TEST CASING. REMOVE PACKER. SPOT 40 SX CMT AT 1400'. TEST CASING. PUMP 175 SX CMT DOWN CASING.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/02/2005 4:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4100' WITH 4 SX CMT. 8/31/05: RUN TUBING WITH PACKER TO 1400'. TEST CASING TO 500# & HELD. PULLED TUBING & REMOVE PACKER. RUN TUBING TO 1400'. PUMP 40 SX COMMON CMT WITH 3% CC. 9/1/05: TEST CASING TO 500# & HELD. PERFORATE CASING AT 600'. 9/2/05: PUMPED 175 SX CMT DOWN CASING 10 SX CMT CIRCULATED TO PIT.


Perfs:

INVOICED
DATE 9-21-05
NO. 2006060454

Remarks: USED 60/40 POZMIX 6% GEL & COMMON CMT WITH 3% CC BY SWIFT SERVICES

Plugged through: CSG

District: 01



Signed

Michael Maier

(TECHNICIAN)

RECEIVED
SEP 14 2005
KCC WICHITA

Form 01-33