

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21832-00-00
Spot: W2SWNW Sec/Twnshp/Rge: 27-29S-8W
3359 feet from S Section Line, 4950 feet from E Section Line
Lease Name: FRANCIS M Well #: 1
County: KINGMAN Total Vertical Depth: 4265 feet

Operator License No.: 6236
Op Name: M.T.M. PETROLEUM
Address: PO BOX 82
SPIVEY, KS 67142

PROD Size: 5.5 feet: 4265
SURF Size: 8.625 feet: 222

#138⁶¹

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 06/09/2005 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: MARVIN MILLER Company: M. T. M. PETROLEUM Phone: (620) 532-3794

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 06/09/2005 5:00 PM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Perfs:

6/9/2005 -- Sanded back 50' above perforations with 5 sacks of cement on top of sand. Shot and pulled casing to 1300' and spotted 35 sacks of cement. Pulled to 700' and spotted 35 sacks of cement. Pulled to 270' and circulated cement to surface with 100 sacks of cement; fell to 150'.

6/10/2005 -- Filled with 2-1/2 yds of slurry mix.

Allied Cementing

60/40 posmix with 4% gel

RECEIVED
KCC DISTRICT #2
JUN 20 2005
WICHITA, KS

Remarks:

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

INVOICED

DATE

9-21-05

WELL NO

2006060465

RECEIVED

SEP 15 2005

KCC WICHITA

Form CP-2/3