

6 061953

8 9-3 163-23,056 -00-0013

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
NE, SEC. 32, T 7 S, R 17 W/E
4290 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30197

Lease Name Carsten Well # 132

Operator: D.C. Dudley and Associates

County Rooks 115.38

Name & Address 1776 Lincoln Street

Well Total Depth 3550 feet

Denver, Co. 80203

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1300

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Rains and Williamson Oil Co. Inc. License Number 5146

Address Hays, Ks.

Company to plug at: Hour: 10:15AM Day: 3 Month: Sept Year: 19 89

Plugging proposal received from Larry Hinderlita

(company name) Rains and Williamson (phone)

were: Order 165 sks 60/40 poz 6% gel 3% cal cl 1 sk f.c. and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis mud between all plugs with good

circulation and no fluid loss.

RECEIVED
STATE CORPORATION COMMISSION
SEP 11 1989
CONSERVATION DIVISION
Wichita, Kansas
9-11-89

Plugging Proposal Received by (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:15AM Day: 3 Month: Sept Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at arb 3450' w/20 sks

2nd plug at 1350' w/40 sks

3rd plug at 800' w/80 sks and 1 sk f.c.

4th plug at 40' w/10 sks

15 sks in rathole

Remarks: B. J. Titan
(If additional description is necessary, use BACK of this form.)

INVOICED
did not observe this plugging.

Signed Gilbert G. Scheck (TECHNICIAN)

Gilbert G. Scheck

DATE 9-18-89

INV. NO. 25894

FORM CP-2/3
Rev. 01-84

NOV 06 1989