

4-020152

SEP 06 2000

9-6-2000

CONSERVATION DIVISION
Wichita, Kansas

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-22,542-0000

SE NE NE /4 SEC. 30, 07 S, 17 W
4290 feet from S section line
330 feet from E section line

Operator license# 7076
Operator: Black Diamond Oil, Inc.
Address: P.O. Box 641
Hays, Kansas 67601

Lease: Griffith Well # 12
County: Rooks 108, 23
Well total depth 3330 feet
Conductor Pipe: 13 3/8 inch @ 89 feet
Surface pipe 8 5/8 Inch @ 1234 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Quality Well Service License# 31925

Address: 249 E. Beth Drive - Sterling, Kansas 67579

Company to plug at: Hour: 12:00 P.M. Day: 1 Month: September Year: 2000

Plugging proposal received from: Richard McIntyre

Company: Quality Well Service Phone: 316-278-2476

Were: Ordered out 240 sxs 60/40 pozmix - 10% gel - 400# hulls.
Shot off casing at 2408'.
Prod Perfs at 2742' - 2746'; 2873' - 2877'; 3063' - 3069'; 3264' - 3268'.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 2:00 P.M., Day: 1 Month: September, Year: 2000

Actual plugging report: 13 3/8" set at 89'w/100 sxs. 8 5/8" set at 1234' w/350 sxs.
5 1/2" set at 3327' w/130 sxs.

Sanded back to 2700' and topped with 5 sxs cement with dump bailer.
Shot casing off at 2408'.
Pulled casing to 1550' - tied onto and pumped 110 sxs with 300# hulls.
Pulled casing to 900' - tied onto and spotted 30 sxs with 100# hulls.
Pulled casing to 500' - tied onto and circulated cement with 85 sxs.
Pulled casing out of hole.
Hole standing full of cement.

Remarks: Allied Cementing Company.
Condition of casing (in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug (in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 1785 GL

I did [X] / did not [] observe the plugging.

Jay P. [Signature]
(agent)

INVOICED
DATE 9/8/00
INV. NO. 8001060615

