

12-29

4-041434

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-22,178 <sup>0000</sup>

SE SE NE /4 SEC. 30, 07 S, 17 W  
2970 feet from S section line  
330 feet from E section line

Operator license# 7011

Lease Griffith well # 11

Operator: Rim Oil Company

County Rooks

Address: 2101 Lincoln Dr.  
Hays, Kansas 67601

Well total depth 3384 feet <sup>109.98</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 221 feet  
w/110 sx.

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Allied Cementing License#    

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 29 Month: December Year: 92

Plugging proposal received from: Marlyn Monroe

Company: Rim Oil Company Phone: 913-434-7475

Were: 5 1/2" casing set @ 3377' w/140 sx. cement. Perf. @ 3304' -  
2784'. D.V. @ 1270'. W.L.M. 3300'. (Fluid level below 1270')  
Well squeezed in annulus also.  
Order 300 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 300# hulls.

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 11:30A.M., Day: 29, Month: December, Year: 92

Actual plugging report: R.I.H. with perforators to 1270'. Perf.  
casing @ 1270'. Rig up cementers to pump 300 sxs. cement with 300#  
hulls in 5 1/2" casing. Max. 700#. 500# S.I.P.  
Hooked-up to 8 5/8" S.P. Pressured up to 1000# P.S.I.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 6 1993

Remarks: (Top of fluid below 1270')  
Condition of casing(in hole): GOOD X BAD     Anhy.plug: YES X NO      
Bottom plug(in place): YES X, CALC X, NO     Dakota plug: YES X, NO      
Plugged through TUBING    , CASING X. Elevation:     GL

1-6-93

I did X observe the plugging.

Dennis L. Hamel

(agent)

Form CP-2/3

INVOICED

DATE 1-8-93  
INV. NO. 37159

170.