

4-020151

SEP 06 2000
9-6-2000

CONSERVATION DIVISION
Wichita, Kansas

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-21, 842-00-00

NW SE NE /4 SEC. 30, 07 S, 17 W
3630 feet from S section line
990 feet from E section line

Operator license# 7076

Lease: Griffith Well # 9
County: Rooks 108.39

Operator: Black Diamond Oil, Inc.

Address: P.O. Box 641
Hays, Kansas 67601 8/30

Well total depth 3335 feet
Conductor Pipe: 13 3/8 inch @ 80 feet
Surface pipe 8 5/8 Inch @ 1237 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Quality Well Service License# 31925

Address: 249 E. Beth Drive - Sterling, Kansas 67579

Company to plug at: Hour: 9:00 P.M. Day: 30 Month: August Year: 2000

Plugging proposal received from: Richard McIntyre

Company: Quality Well Service Phone: 316-278-2476

Were: Ordered out 240 sxs 60/40 pozmix - 10% gel - 400# hulls.
Shot off casing at 2420'.
Prod Perfs at 2740' - 2746'; 2969' - 2981'; 3063' - 3071'; 3261' - 3265'.

Plugging Proposal Received by: Richard Williams

Plugging operations attended by agent? All , Part , None

Completed: Hour: 11:15 A.M., Day: 30 Month: August, Year: 2000

Actual plugging report: 13 3/8" set at 80'. 8 5/8" set at 1237' w/450 sxs.
5 1/2" set at 3327' w/135 sxs.

Sanded back to 2700' and topped with 5 sxs cement with dump bailer.

Shot casing off at 2420'.

Pulled casing to 1550' - tied onto and pumped 110 sxs with 300# hulls.

Pulled casing to 900' - tied onto and spotted 40 sxs with 100# hulls.

Pulled casing to 450' - tied onto and circulated cement with 85 sxs.

Pulled casing out of hole.

Hole standing full of cement.

Remarks: Allied Cementing Company.

Condition of casing (in hole): GOOD BAD

Bottom plug (in place): YES , CALC , NO

Plugged through TUBING , CASING . Elevation: 1786 GL

I did / did not observe the plugging.

[Signature]
(agent)

INVOICED
9/8/00
2001060615

[Signature]