

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-163-21,551-00-00 (of this well).
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR W J Inc. OPERATOR'S LICENSE NO. 9811

ADDRESS RR #3 Ellis, Ks. 67637 PHONE # (913) 726-4408

LEASE (FARM) Bittel WELL NO. 1 WELL LOCATION SW SW NW COUNTY Rooks

SEC. 21 TWP. 7 RGE. 17W (E) or (W) TOTAL DEPTH 3490' PLUG BACK TD

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 13 3/8" SET AT 128' CEMENTED WITH 215 SACKS
8 5/8" SET AT 1198' CEMENTED WITH 275 SACKS

CASING SIZE 4 1/2" SET AT 3416' CEMENTED WITH 100 SACKS

PERFORATED AT 3179' 3150-51' 3123-24' 3109' 3044-56' 2848-50' 2780-81'

CONDITION OF WELL: 2720-24'
GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING WE WILL PLUG WELL ACCORDING TO THE RULES AND REGULATIONS OF THE STATE OF KANSAS.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? IS ACO-1 FILED?
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

W J Inc. PHONE # (913) 726-4408

ADDRESS RR #3 Ellis, KS. 67637

PLUGGING CONTRACTOR Kelso Casing Pulling, Inc. LICENSE NO. 6050

ADDRESS P.O.Box 347 Chase, KS. 67524 PHONE # (316) 938-2943

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Kesley Bittel
(Operator or Agent)

DATE: 10-15-90

4

RECEIVED
STATE CORPORATION COMMISSION
11-15-90
NOV 15 1990
CONSERVATION DIVISION
Wichita, Kansas

6/9/91

REPLACEMENT CARD

LIBERTY ENTERPRISES, INC.
308 W. MILL

#1 BITTEL

21-7-17W
SW SW NW

PLAINVILLE, KS 67663


CONTR PIONEER DRLG. CO., INC.

CTY ROOKS

GEOL

FIELD

RIFFE EXT (1/2 E)



ELV 1749 KB SPD 2/11/82 CARD ISSUED 9/23/82 IP P 5 BO & 55 BWPD

1744 GL

SHAW (TOR) 2720-2781 OA

API 15-163-21,551

LKC 2948-3179 OA

LOG	Tops	Depth/Datum
TOP		2691- 942
HEEB		2904-1155
TOR		2927-1178
LANS		2947-1198
BKC		3181-1432
ARB		3324-1575
RTD		3490-1741

13 3/8 " COND AT 128/215SX; 8 5/8 " 1198/275SX; 4 1/2 " 3416/100SX

DST (1) 3018-3060 (LKC) / 30-60-30-30, REC 20' HOCM, 200' WOCM, SIP 1090-1040#, FP 41-83 / 100-142#

DST (2) 3096-3140 (LKC) / 30-60-30-30, REC 80' SL WTRY DM, W / FEW SPKS OIL, SIP 916-775#, FP 50-66 / 75-91#

DST (3) 3136-3190 (LKC) / 30-60-30-30, REC. 45' DM, SIP 950-734#, FP 50-50 / 58-58#

MICT - CO, PF (LKC) 1 / 3179, 1 / 3150-51, 1 / 3123-24, 1 / 3109, 8 / 3044-3056, 8 / 2948-2950, AC 1500G, SWB DWN, GSP, PF (TOP) 1 / 2780-81 & 16 / 2720-24, AC 2500G (MA) & 2500G (RET), SWB DWM, GSO, POP, P 5 BO & 55 BWPD (GR 38%), COMMINGLED, 3/3/83

INFO RELEASED: 4/28/83 - WAS ABD LOC

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

RECEIVED
STATE CORPORATION COMMISSION

NOV 15 1990

CONSERVATION DIVISION
Wichita, Kansas

Wesley Bittel

#9811

WS Inc.

RR#3

Ellis, Mo. 67637

(913) 726-4408

Wesley



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
 KEITH R. HENLEY CHAIRMAN
 RICH KOWALEWSKI COMMISSIONER
 JACK SHRIVER COMMISSIONER
 JUDITH MCCONNELL EXECUTIVE DIRECTOR
 FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION
 SHARI FEIST ALBRECHT, DIRECTOR
 200 Colorado Derby Bldg.
 202 W. 1st Street
 Wichita, KS 67202-1286
 (316) 263-3238

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

November 16, 1990

W J, Inc.
 R.R. #3
 Ellis, KS 67637

Bittel #1
 SW SW NW 21-07-17W
 Rooks County, KS
 API No. 15-163-21,551-0000

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
 Production Supervisor

District: #4, 2301 E. 13th
 Hays, KS 67601
 (913) 628 - 1200