

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
500 INSURANCE BUILDING
212 NORTH MARKET
WICHITA 2, KANSAS

WELL PLUGGING APPLICATION FORM
File One Copy

RECEIVED
STATE CORPORATION COMMISSION

JUL 25 1967
7-25-67
CONSERVATION DIVISION
Wichita, Kansas

Lease Owner Chief Drilling Co., Inc. 15-163-20034-00-00
(Applicant)
Address Box 797 - Great Bend, Kansas 67530

Lease (Farm Name) STAMBACH Well No. 1

Well Location SE SW SW Sec. 33 Twp. 7S Rge. (E) 17 (W)

County Rooks Field Name (If any) _____

Total Depth 3440' Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A x

Was well log filed with application? Yes If not, explain: _____

Date and hour plugging is desired to begin 7/21/67

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission.

Name of the person on the lease in charge of well owner Marion L. Burris

Address Hoisington, Kansas 67544

Plugging Contractor Chief Drilling Co., Inc. License No. _____

Address Box 797 - Great Bend, Kansas 67530

Invoice covering assessment for plugging this well should be sent to Chief Drlg. Co., Inc.

Address Box 797 - Great Bend, Kansas 67530

and payment will be guaranteed by applicant.

Signed: *V. Richard Hoover*
Applicant or Acting Agent

Date: 7/24/67

15-163-2003400-00

WELL LOG

Chief Drilling Co., Inc.
Box 797
Great Bend, Kansas 67530

STAMBACH #1
SE SW SW Sec. 33-7S-17W
Rooks County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 7-11-67
Completed: 7-21-67

Casing Record: 8-5/8" @ 205' w/150 sacks 60/40 Pozmix.

DRY & ABANDONED

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Clay	0	205	1936 Gr.
Shale & Shells	205	460	1938 D.F.
Sand & Shale	460	1010	1941 K.B.
Red Bed	1010	1250	
Red Bed & Shale	1250	1305	
Anhydrite	1305	1340	
Shale & Shells	1340	1788	
Shale & Lime	1788	2898	
Lime	2898	3025	
Lime & Shale	3025	3100	
Lime	3100	3280	
Lime & Shale	3280	3405	
Dolomite	3405	3440	
Total Depth	3440		

<u>FORMATION TOPS</u>	
Anhydrite	1305 + 636
Topeka	2858 - 917
Heebner	3071 -1130
Toronto	3095 -1154
Lansing	3114 -1173
Base Kansas City	3345 -1404
Arbuckle	3407 -1466
Total Depth	3440 -1499

STATE OF KANSAS, COUNTY OF BARTON) SS


I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the SE SW SW Section 33-7S-17W, Rooks County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover
V. Richard Hoover, President

Subscribed and sworn to before me this 24th day of July, 1967.

Carmen R. Cook
Carmen R. Cook, Notary Public



Commission expires: Dec. 12, 1970.

RECEIVED
STATE CORPORATION COMMISSION

JUL 25 1967

7-25-67

CONSERVATION DIVISION
Wichita, Kansas



15-163-20034-00-00

ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

July 24, 1967

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Stambach
Description	SE SW SW 33-7-17W
County	Rooks
Total Depth	3440
Plugging Contractor	Co. Tools


Chief Drilling Co., Inc.
Box 797
Great Bend, Kansas 67530

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Very truly yours,


J. P. Roberts, Administrator

Mr. Leo Massey Box 582 Hays, Kansas 67601
is hereby assigned to supervise the plugging of the above named well.