

6030175

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-179-20,736-00-00

SW, SEC. 19, T 6 S, R 27 (W)E

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9123

Lease Name MAIN Well # 1-19

Operator: DIAMOND SHAMROCK

County SHERIDAN

Name & Address BOX 631 ~~AMARILLO~~

Well Total Depth 4771 155.06 feet

AMARILLO, TEXAS

Conductor Pipe: Size _____ feet

*Joy Cody
316-565-7772*

(806) 378-2500 79173

Surface Casing: Size 8 5/8 feet 307

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor BIG SPRINGS DRUG. INC. License Number 143

Address BOX 8287 MUNGER STA. 400N. WOODLAWN SUITE 29 WICHITA, Ks. 67208

Company to plug at: Hour: AM Day: 18 Month: 4 Year: 19 84

Plugging proposal received from HARRY

(company name) DIAMOND SHAMROCK (phone) _____

were: SPOT WITH DRILL PIPE 25 SX. @ 4600 (BREAK CIRC.)

25 SX. @ 2430

100 SX. @ 1500

40 SX. @ 300

HALLIBURTON 10 SX. @ 40 SBP 10 SX. RATHOLE (CIRC.)

50/50oz 6 PEGEL 3 1/2 cc 2 SX. FLO-SEAL Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:40AM Day: 18 Month: 4 Year: 19 84

ACTUAL PLUGGING REPORT AS ABOVE

Remarks: THEY LOST CIRC. @ BOTTOM NEAR 4700 REAMED THE HOLE TO 4690 BECAUSE HOLE CAVED IN ON THEM
ELLEV. 2676
ANHY 2426 THEY QUIT AT 4690 REGAINED CIRC. AND TESTED
ARB 4602 THEN PLUGGED.

Remarks: _____ (If additional description is necessary, use BACK of this form.)

I (did/did not) observe this plugging.

DATE 4-30-84

Signed Carl Goodson (TECHNICIAN)

INV. NO. 1293

RECEIVED
STATE CORPORATION COMMISSION
04-30-1984
APR 30 1984
CONSERVATION DIVISION
Wichita, Kansas

4-18 MAY 03 1984