

6 031517

API NUMBER 15-

1962

3-27  
15-179-05517-00-00  
new

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE NW NW, SEC. 12, T 6 S, R 27 W/E

4950 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5916

Lease Name Adell LKC Well # 210

Operator: Conoco Inc.

County Sheridan 124.80

Name & Address Box 267

Well Total Depth 3840 feet

Great Bend, Ks. 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 191

Abandoned Oil Well Gas Well Input Well XX SWD Well D&A

Other well as hereinafter indicated 8906

Plugging Contractor Allied Cement Co. License Number

Address Russell, Ks.

Company to plug at: Hour: Day: 27 Month: Mar Year: 19 91

Plugging proposal received from David Lorenzo

(company name) Conoco (phone)

were: 8 5/8 set at 198 w/200 sks cwc. 5 1/2 set at 3839 w/225 sks. PBDT 3805.

Perf 3587 - 3784. Shots at 2130 anhy 1325 Kiowa. Order 400 sks.

65/35 poz 8% gel Allied Cement Co. Larue Water Trucks. Wireline shot 2200. Hole open.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 10 1991  
04-10-91  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 12:00PM Day: 27 Month: Mar Year: 19 91

ACTUAL PLUGGING REPORT Sq annulus w/100 sks cement blend to max psi

500 lb. Close in psi 150 lbs. Sq 8 5/8 w/300 sks cement blend to max psi 500 lbs.

Close in psi 300 lbs. Plug complete.

INVOICED

Remarks: 4-17-91

DATE (If additional description is necessary, use BACK of this form.)

INV. NO. 3/555 Observe this plugging.

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow

Note - question re: spot location  
I think it is NE 1/4 NW 1/4