

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25079-00-01
Spot: N2SENE Sec/Twnshp/Rge: 5-14S-20W
3660 feet from S Section Line, 560 feet from E Section Line
Lease Name: GABEL Well #: 1
County: ELLIS Total Vertical Depth: 3970 feet

Operator License No.: 31240
Op Name: ENTERPRISE INC
Address: 2708 BARCLAY DR.
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	207		

#129⁰³

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/30/2005 12:00 AM
Plug Co. License No.: 30076 Plug Co. Name: ANDERSON, ANDY DBA A & A PRODUCTION
Proposal Rcvd. from: DARREL ANDERSON Company: ANDERSON, ANDY DBA A & A PR Phone: (785) 421-6266

Proposed Plugging Method: Ordered 215 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: NONE
Date/Time Plugging Completed: 08/30/2005 4:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

1st. Plug at 3900' w/25 sxs.
2nd. Plug at 1600' w/25 sxs.
3rd. Plug at 675' w/100 sxs.
4th. Plug at 260' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Richard Williams

(TECHNICIAN)

RECEIVED

SEP 02 2005

KCC WICHITA

INVOICED

DATE

9-2-05

WV. NO

2006060430

Form CP-2/3

AUG 31 2005