

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24378-00-00
Spot: NENESE Sec/Twnshp/Rge: 4-20S-22W
2150 feet from S Section Line, 360 feet from E Section Line
Lease Name: GROSS Well #: 1
County: NESS Total Vertical Depth: 4496 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	243		#146 12

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/30/2005 6:00 AM
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY
Proposal Rcvd. from: GARY TALBOT Company: STERLING DRILLING COMPANY Phone: (620) 672-9508

Proposed Plugging Method: 1ST PLUG AT 1530' WITH 50 SX CMT. 2ND PLUG AT 780' WITH 80 SX CMT. 3RD PLUG AT 270'W TIH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: NONE
Date/Time Plugging Completed: 08/30/2005 8:00 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

Perfs:


1ST PLUG AT 1530' WITH 50 SX CMT. 2ND PLUG AT 780' WITH 80 SX CMT. 3RD PLUG AT 270'W TIH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

INVOICED
DATE 9-2-05
INV. NO 2006060431

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed

Jerry W. Stapleton PIRT II
(TECHNICIAN)

RECEIVED
SEP 02 2005
KCC WICHITA

Form CP 2/3