

4-020101

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API number: 15-193-20,648-0000

5-8  
SW SE SW /4 SEC. 02, 06 S, 33 W  
330 feet from S section line  
3630 feet from E section line

Operator license# 03602

Lease: J & B, Inc. Well # 1-1402

Operator: Philpott Oil & Gas Co., Inc.  
Address: 408 Main  
P.O. Box 450  
Atwood, Kansas 67730

County: Thomas 150.47  
Well total depth 4630 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8% Inch @ 261 feet

Aband. oil well \_\_\_\_\_, Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A X

Plugging contractor: Murfin Drilling Co., Inc. License# 30606

Address: 250 N. Water, Suite 300, Wichita, Kansas 67202

Company to plug at: Hour: \_\_\_\_\_ Day: 08 Month: May Year: 1996

Plugging proposal received from: Keith Van Pelt

Company: Murfin Drilling Co., Inc. Phone: 913/ 443-1131

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2730 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1910 feet with 100 sacks

3rd plug @ 310 feet with 40 sacks

4th plug @ 40 feet with 10 sacks

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 17 1996

5-17-96  
CONSERVATION DIVISION  
WICHITA, KS

Plugging Proposal Received by: Ken Kuhn

Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour: 11:30 PM, Day: 08, Month: May, Year: 1996

Actual plugging report: Hole reported plugged as above.

Order 190 sx 60/40 pozmix w/ 6% gel and 2.0 sx celloflake or flowcel.

Remarks: Allied Cementing performed the cement job.

Condition of casing(in hole): GOOD X BAD \_\_\_\_\_ Anhy.plug: YES X NO \_\_\_\_\_

Bottom plug(in place): YES X, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES X, NO \_\_\_\_\_

Plugged through TUBING \_\_\_\_\_, CASING X. Elevation: 3110 GL

I did X observe the plugging.

Ken Kuhn  
(agent)

Form CP-2/3

**INVOICED**  
DATE 5-30-96  
INV. NO. 45-693  
5-8

JUL 17 1996