

1-5 4-031887

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-193-20029-000000

NWSE
C SW SE /4 SEC. 02, 06 S, 33 W
660 feet from S section line
1980 feet from E section line

Operator license# 5144 Lease Turner well # 1

Operator: Mull Drilling Company County Thomas

Address: P.O. Box 2758 Well total depth 2915 feet
Wichita, Kansas 67201 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 291 feet

94.74

Aband. oil well X, Gas well __, Input well __, SWD __, D & A __

Plugging contractor: Cheyenne Well Service License# 1760

Address: Ness City, Kansas

Company to plug at: Hour: A.M. Day: 5 Month: January Year: 94

Plugging proposal received from: Terry Roane

Company: Mull Drilling Company Phone: _____

Were: Order 300 sxs. common cement - 200 sxs. 50/50 pozmix - 4% gel.
Plugged in 05-28-70 - D&A - Rains & Williamson Drilling.
Due to low anhydrite @ 2800+ - 1590' stacked out - 447' wireline
260' fluid.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 2:30 P.M., Day: 5, Month: January, Year: 94

Actual plugging report: 8 5/8" set @ 291' cwc. Ran 2 7/8" tubing to
1593' tagged cement. Pumped down 2 7/8" - 300 sxs. common cement.
Pulled 2 7/8" to 693'. Mix and pump down 2 7/8" - 160 sxs. cement blend
to circulate. Laid down 2 7/8" topped off 8 5/8" with 20 sxs. cement
blend. Used total 480 sxs. cement. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO
Bottom plug(in place): YES \, CALC \, NO X Dakota plug: YES X, NO
Plugged through TUBING X, CASING \. Elevation: \ GL

RECEIVED STATE CORPORATION COMMISSION

JAN 20 1994

CONSERVATION DIVISION Wichita, Kansas

I did observe the plugging. Carl Goodrow

INVOICED

DATE 1-28-94

INV. NO. 39825

1-5

HD

(agent)

Form CP-2/3