

4-060321

6-25

158R

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-193-20,593-0000

NW SE SW /4 SEC. 02, 06 S, 33 W
990 feet from S section line
3630 feet from E section line

Operator license# 5184

Lease J & B Inc. well # 1

Operator: Shields Oil Producers, Inc.

County Thomas

Address: Shields Building
Russell, Kansas 67665

Well total depth 4313 feet ^{140.17}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 264 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Shields Drilling Company License# 5655

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:15A.M. Day: 25 Month: June Year: 92

Plugging proposal received from: Burt Berry

Company: Shields Drilling Company Phone: 913-483-3141

Were: Order 200 sxs. 60/40 posmix - 6% gel. - 1/4# flocele per sx.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 8:15A.M., Day: 25, Month: June, Year: 92

Actual plugging report:

1st. plug at 2750' w/25 sks. - Anhydrite 2724' - 2762'.

2nd. plug at 1915' w/100 sks. - Dakota 1614' - 1914'.

3rd. plug at 315' w/40 sks. - Surface pipe to 264'.

4th. plug at 40' w/10 sks. -

Rathole with 15 sks.

Mousehole with 10 sks.

RECEIVED
STATE CORPORATION COMMISSION

JUL 6 1992

CONSERVATION DIVISION
Wichita, Kansas

7-6-92

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: 3114 GL

INVOICED
I did / did not observe the plugging.

Herb Deines

DATE 7-17-92

CHK. NO. 35694

J.H.S.

(agent)

Form CP-2/3