

9-23

215
R

4-031762

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-193-20,211-00-00

C SW SE /4 SEC 17, 06 S, 35 W
660 feet from S section line
1980 feet from E section line

Operator license# 5364 Lease Glenn well # 1

Operator: Beren Corporation County Thomas

Address: P.O. Box 723 Well total depth 4855 feet
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 328 feet

157.79

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: B.J. Services License# -

Address: Oakley, Kansas

Company to plug at: Hour: A.M. Day: 23 Month: September Year: 92

Plugging proposal received from: George Jorgensen

Company: Beren Corporation Phone: _____

Were: Order 400 sx. 60/40 pozmix - 10% gel. - 500# hulls.
Hole open to perf. Pulled rods and tubing.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 1:00P.M., Day: 23, Month: September, Year: 92

Actual plugging report: 8 5/8" set @ 328' w/250 sx. cwc. 4 1/2" set @
4650' w/275 sx. Perf's 4541' - 4546'. Free point 1800'. Pumped bottom
plug with 100 sx. cement blend with 250# hulls mixed in. Shot off casing.
Spotted 80 sx. cement blend. Laid down casing. Squeezed 8 5/8" with
total 400 sx. cement blend with 500# hulls mixed in. Max. P.S.I. 300#.
Close in P.S.I. 150#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
10-8-92
OCT 8 1992

Remarks: _____
Condition of casing(in hole): GOOD BAD Any plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING _____, CASING . Elevation: _____ GL _____

I did / did not observe the plugging. Carl Goodrow

DATE 11-17-92

INV. NO. 36788

(agent)

Form CP-2/3

DEC 11 1992