

10-31 15193-20203-0000

To: 6 031294
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1980
NW SE, SEC. 16, T. 6 S. R. 35 E. S. 36
1980 feet from S section 1000e
1980 feet from E section 11-20-89
Lease Name Nickel Well #
County Thomas 156.00
Wichita, Kansas

TECHNICIAN'S PLUGGING REPORT
Operator License # 5364

Operator: Beren Corp
Name & Address: Box 723
Hays, Ks. 67601

Well Total Depth 4800 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 304

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor B. J. Titan License Number
Address Oakley

Company to plug at: Hour: AM Day: 31 Month: Oct Year: 19 89

Plugging proposal received from George Jorgenson
(company name) (phone)

were: 8 5/8" set at 304' w/250 sks. 5 1/2" set at 4575' w/275 sks.

PBTD 4542'. Perf 4500' - 04'. Squeezed at 1380' w/150 sks. Shots at 2900'. Order 325 sks

65/35 poz 10% gel 2% 500# hulls. B. J. Titan Cement Co. Hensley, Wellbrock Water Trucks.

Laid out 147 joints of tubing and rods. Hole open.

Plugging Proposal Received by Carl
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:00AM Day: 31 Month: Oct Year: 19 89

ACTUAL PLUGGING REPORT Squeezed 5 1/2" w/225 sks cement blend w/
400# hulls to max psi 1000#. Close in psi 500#. Squeeze 8 5/8" annulus w/100 sks cement blend
w/100# hulls mixed in to max psi 400#. Close in psi 400#. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

INVOICED

DATE 12-4-89
INV. NO. 26544

Signed Carl Goodrow
(TECHNICIAN)