

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21500-00-01
Spot: SESWNW Sec/Twnshp/Rge: 10-11S-17W
2970 feet from S Section Line, 4290 feet from E Section Line
Lease Name: EVELYN OWWO Well #: 1
County: ELLIS Total Vertical Depth: 3388 feet

Operator License No.: 30537
Op Name: VENTURE RESOURCES, INC.
Address: 2110 S. GILPIN PO BOX 101234
DENVER, CO 30250

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3370	0	w/150 sxs cmt
SURF	8.625	359	0	w/300 sxs cmt

8 110"

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/30/2005 1:00 PM
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC
Proposal Rcvd. from: JOHN CEARLEY Company: VENTURE RESOURCES, INC. Phone: (785) 731-5073

Proposed Plugging Method: Ordered 160 sxs 60/40 pozmix - 10% gel - 500# hulls.
PBTD 3360'. Casing leak. Fluid at 250'. Tagged junk in bottom at 3302'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/30/2005 3:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Chito's RIH with tubing to 1507'.
Swift rigged to tubing and pumped 105 sxs cement with 400# hulls mixed in.
Pulled tubing to 1000' - pumped 80 sxs 60/40 pozmix with 100# hulls mixed in - circulated cement to surface.
Pulled tubing - tied onto 4 1/2" casing with a swedge and pumped 30 sxs.
Max. P.S.I. 500#. S.I.P. 200#.
Tied onto 8 5/8" casing - pumped 5 sxs cement with Max. P.S.I. 150#.
Blew small hole in head. Backside stayed full.

Perfs:

Top	Bot	Thru	Comments
3328	3332		
3314	3320		
3302	3312		

Remarks: SWIFT CEMENTING & ACID SERVICES-TICKET #8620.

Plugged through: TBG

District: 04

HO

Signed

Pat Staab

(TECHNICIAN)

INVOICED

DATE 9.2.05

WIL NO 2006060438

RECEIVED

SEP 02 2005

KCC WICHITA

Form CP-2/3

AUG 31 2005

LIBERTY ENTERPRISES
 308 W MILL
 PLAINVILLE, KS 67663
 CONTR PIONEER DRILLING CO INC
 #1 EVELYN "OWWO"
 10-11-17W
 SE SW NW
 CITY ELLIS

GEOL _____ FIELD UPPER TURKVILLE EXT (1/4 E)

E 1805 KB CM 7/20/81
 CA ISSUED 1/12/81
 P 17 BO & 14 BWPD
 CONG 3302-3332 OA

+	+	+
+	+	+
+	+	+

API 15-051-21,500-A

LOG	TOPS	DEPTH	DATUM
*ANH		1030	+ 775
*B ANH		1062	+ 743
TOP		2250	- 445
HEEB		2978	- 1173
TOR		3003	- 1198
LANS		3023	- 1218
B KC		3279	- 1474
CONG		3304	- 1499
RE-WORK ARB		3371	- 1566
ARB		3379	- 1574
RTD		3387	- 1582
LTD		3388	- 1583
* SMP TOPS			

OLD INFO: OPERATOR WAS TGT PETRO CORP,
 #1 E M SIMPSON, SPD 8/18/78, SET 8-
 5/8" 359/300SX, COMP AS D&A/ARB
 8/27/78

DST (1) 3102-18/30-45-90-60, 230' MW,
 SIP 884-884#, FP 18-55#, 64-128#,
 BHT 109°

NEW INFO: RE-ENTERED 7/20/81, WSH DWN
 TO 3382', SET 4 1/2" @ 3370, MICT - CO,
 PF 12/3302-3312, 6/3314-3320, 4/3328-
 3332, AC 2000 GAL & 30 BS, FRAC FL
 (AMT NA) & 75,000# SD, TSTD, POP,
 P 17 BOPO & 14 BWPD, 8/1/81

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS