

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-21,999-00-00

SW 1/4 Sec. 7, T 7 S, R 17 W 1/2

330 feet from ~~N/S~~ section line

1650 feet from W 1/2 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6509

Lease Name Miller-American Well # 1

Operator: Cla-Mar Oil Company
Name & Address 2705 Vine - Suite 8
Hays, Kansas 67601

County Rooks

Well Total Depth 3441 feet 111.83

Conductor Pipe: Size - feet -

Surface Casing: Size 8 5/8" feet 290

Abandoned Oil Well - Gas Well - Input Well - SWD Well - D&A

Other well as hereinafter indicated -

Plugging Contractor Red Tiger Drlg. Co. License Number 5302

Address 1720 Kansas State Bank Bldg. Wichita, Ks. 67202

Company to plug at: Hour: 2:45 AM Day: 9th Month: April Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO Bill Ayres

(company name) Red Tiger Drlg. Co. (phone) -

were: Spot 1st plug at 3437' w/ 20 sx. 2nd plug at 1354' w/ 20 sx. 3rd plug at 710' w/ 80 sx. 4th plug at 340' w/ 40 sx. 5th plug - solid bridge w/ 1 sx. hulls 10 sx emt. at 40' 10 sx. rat hole, no mouse hole. Order 180 sx. 50/50 posmix, 4 7/8 gal., 3 7/8 gal. cl., 1-8 5/8" plug

Signed Edwin A. Schumacher
(TECHNICIAN)

Plugging Operations attended by Agent?: All - Part - None

Operations Completed: Hour: 2:45 AM Day: 9 Month: April Year: 19 83

ACTUAL PLUGGING REPORT -

Remarks: Elevation - 1882', Anhydrite - 1342', did penetrate
ar buckle, (Allied Cementing)

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed Edwin A. Schumacher
(TECHNICIAN)

INVOICED

DATE 4-22-83
INV. NO. 4101-W

RECEIVED
STATE CORPORATION COMMISSION
04-18-1983
APR 18 1983
CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 9-82