

6 030547

15-181-20068-00-00

R

API NUMBER 15-

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

CNESE, SEC. 13, T. 6 S, R. 38 W

1980 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6499

Lease Name FINEGAN Well # 1

Operator: ABRAXAS PET. CORP.

County SHERMAN 162.50

Name & Address P.O. Box 17485

Well Total Depth 5000' feet

SAN ANTONIO, TEXAS

Conductor Pipe: Size _____ feet

78217

Surface Casing: Size 8 5/8 feet 319' ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING PULLING License Number 6050

Address CHASE KANSAS 67524

Company to plug at: Hour: PM Day: 26 Month: 8 Year: 19 85

Plugging proposal received from RONNIE

(company name) KELSO CASING. PULLING (phone) _____

were: 8 3/8 SET @ 319' w/ 220 SX. 4 1/2 SET @ 4978' w/ 200 SX. PBTD 4936'

TOP PERF. 4602-10 SQUEEZED 4612-18 ORDER SAND COM. CNT.

RECOVERED 2814 4 1/2" CASING. ORDER 180 SX. 60/40 PZ 8/6 GEL 3% CC

40 SX. GEL 3 SX. HULLS B.J. TITON CNT. CO. NEUMAN WATER TRUCKS.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1:PM Day: 26 Month: 8 Year: 19 85

ACTUAL PLUGGING REPORT Dump SAND ON PBTD TO 3550 w/ 4 SX. COM. CNT. ON TOP.

TOP PLUG. PUMP DOWN 8 3/8 w/ 2 SX. HULLS 6 SX. GEL. 100 SX. CNT. MIX

34 SX. GEL. 8 3/8 W.P. 80 SX. CNT. MIX. MAX. PSI 400* CLOSED 200*

PLUG. COMPLETE

STATE CORPORATION COMMISSION

SEP 3 1985 9-3-85

CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

8, 30-85
mjs

INVOICED

DATE SEP 10 1985

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 9943