

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22351-00-00
Spot: CSWSWSW Sec/Twnshp/Rge: 17-7S-17W
330 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: LOOK Well Number: 2
County: ROOKS Total Vertical Depth: 3270 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 1188 350 SX CMT
Production: Size 5.5 feet: 3264 150 SX CMT
Liner: Size feet: 106.28

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/06/2001 10:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 400# hulls.
Perfs 2930' - 3133'. PBSD 3165'.
Sand back to 2650' w/5 sxs cement on top.
Shoot off casing at 2400'+ and plug and spot plugs thru casing.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 09/06/2001 1:00 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Sanded back to 2647' w/5 sxs cement on top.
No pipe recovery.
Shot at 2065'.
Allied pumped 50 sxs 60/40 pozmix - 10% gel, followed with 200 sxs with 400# hulls.
Max. P.S.I. 500#. S.I.P. 150#.
8 5/8" full of cement at surface.
Note: No pipe recovery - cement in 8 5/8" - 5 1/2".

RECEIVED
SEP 13 2001
09-13-2001
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

MD

Signed

Richard Williams

(TECHNICIAN)

INVOICED


Form CP-2/3

DATE 9-13-01

INV. NO. 2002060459

SEP 12 2001

BLACK BEAUTY OIL COMPANY REPLACEMENT CARD
 P.O. BOX 511 #2 LOOK 17-7-17W
 HAYS, KS. 67601 SW SW SW
 CONTR PIONEER DRILLING #2 CTY ROOKS
 GEOL LAWRENCE F. GRAY FIELD RIFFE



ELV 1751 KB SPD 5/9/84 CARD ISSUED 11/1/84 IP P 4 BO & 1 BWPD
 1746 GL DRLG COMP 5/14/84 ARB OH 3264-3270
 API 15-163-22,351

LOG	Tops	Depth/Datum
ANH	1182+	569
B/ANH	1216+	535
TOP	2677-	926
HEEB	2888-	1137
TOR	2910-	1159
LANS	2930-	1179
BKC	3161-	1410
ARB	3259-	1508
LTD	3265-	1514
RTD	3270-	1519

8 5/8 " 1188 / 425 SX, 5 1/2 " 3264 / 140 SX
 NS IN SD FROM 685-900
 NO CORES OR DSTS
 MICT - CO. (ARB OH), SWB DWN, SO, NAT, POP, P 4 BO & 1
 BWPD

INFO RELEASED: 2/5/87 - WAS OIL WELL - TIGHT HOLE