

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-22, 114 ✓ 00-00

SW-NW-5W SEC. 17, T 7S, R 17W/E

1650 FEET FROM N/S SECTION LINE

330 FEET FROM W/E SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5140

LEASE NAME GROVER WELL # 1

OPERATOR: FRONTIER OIL COMPANY
NAME & ADDRESS 1720 KANS. ST. BLDG.
WICHITA, Mo. 67202

COUNTY: ROOKS 91 108.55

WELL TOTAL DEPTH 3340 FEET

CONDUCTOR PIPE: SIZE 13 3/8 FEET 169

SURFACE CASING: SIZE 8 5/8 FEET 1244

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR RED TIGER DRILG. Co LICENSE NUMBER 5302

ADDRESS 1720 KANS. ST. BLDG. WICHITA, Mo. 67202

COMPANY TO PLUG AT: HOUR: 2:00 PM DAY: 20th MONTH: AUG. YEAR: 1983

PLUGGING PROPOSAL RECEIVED FROM KEN LYLE

(COMPANY NAME) RED TIGER DRILG. (PHONE) 316-263-1201

WERE: 13 3/8" - 169 FT COND. CUC #/160 1st COMMON - 2% GEL - 3% CA-CL.

8 5/8" - 1244 FT SP. CUC #/600 2nd 60/40 Poz. 2% GEL - 3% CA-CL. (ALLIED)

ORDER 200 2nd 50/50 Pozmix 6% GEL - 3% CA-CL AND 8 5/8" PLUG

SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

ARTBUCKLE @ 3330 FT ELV. 1763 - ANN. 1241

PLUGGING PROPOSAL RECEIVED BY Maurice Schmidt (TECHNICIAN) 801C

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ NONE

OPERATIONS COMPLETED: HOUR: 2:00 PM DAY: 20th MONTH: AUG. YEAR: 1983

ACTUAL PLUGGING REPORT

ORDERED 200 2nd 50/50 Pozmix 6% GEL - 3% CA-CL AND 8 5/8" PLUG

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS

1st Plug @ 3300 FT #/20 1st CNT., 2nd Plug @ 1260 FT #/20 1st CNT.

3rd Plug @ 660 FT #/100 1st CNT., 4th Plug @ 240 FT #/40 1st CNT.

5th Plug ^{SAVED BRIDGE} HULLS-PLUG @ 40 FT #/10 1st CNT., 10 RAT HOLE (CIRCUMFERE)

REMARKS: CEMENTED BY ALLIED CNT.

RECEIVED
STATE CORPORATION COMMISSION
08-29-1983
AUG 29 1983

CONSERVATION DIVISION
Wichita, Kansas

I (DID / DID NOT) OBSERVE THIS PLUGGING.

SIGNED Maurice Schmidt (TECHNICIAN) 801C

INVOICED
DATE 9-2-83
INV. NO. 5401-W

FORM CP-2/3
32 REV. 6-83