

15-103-22133-00-02

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- -

5W-5W-5W, Sec. 7, T 7 S, R 17W

feet from N/S section line

feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7884

Lease Name Miller 'A' Well # 1

Operator: M.W.M Oil & Gas Inc.
Name & Address: 1313 S. Main Rd
Wichita, Kansas
67209

County Rooks

Well Total Depth 3408 feet 110.76

Conductor Pipe: Size 13 3/8 feet 91' w/ 130 sy cmt

Surface Casing: Size 8 1/2 feet 1334' w/ 600 sy cmt

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing License Number

Address Chase, Kansas

Company to plug at: Hour: 8:00AM Day: 31 Month: 5 Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Millard Kelso

(company name) Kelso Casing (phone)

were: 5 1/2" set @ 3405' w/ 175 sy. Top Perf 3260'

P.B. 5 sy cmt followed w/ sand to 3200 + 5 more sy cmt.

Ordered 190 sy 5050 poz, 80 gal, 3% cc, 50 sy gd, 4 sy lulls + w. plug

Recovered approx. 2094' csg.

Signed Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:00AM Day: 31 Month: 5 Year: 1984

ACTUAL PLUGGING REPORT

Imped in 8 1/2" -> 4 lulls -> 5 gel -> 40 sy cmt -> 10 sy gel -> 100 sy cmt. -> 5 sy gel -> Rel. Plug -> 50 sy cmt

MAX 1000# P.S.T

Shut-in 1000# P.S.T

cmt by Allied

Remarks:

RECEIVED
STATE CORPORATION COMMISSION

JUN 04 1984

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated

and that I (did) / did not) observe this plugging.

Signed Dennis L. Hamel
(TECHNICIAN)

INVOICED

DATE 6-5-84

INV. NO. 1814