

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22020-00-00
Spot: N2NENWSW Sec/Twnshp/Rge: 18-7S-17W
2910 feet from N Section Line, 990 feet from W Section Line
Lease/Unit Name: R MILLER Well Number: 1-C
County: ROOKS Total Vertical Depth: 3410 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 1274 500 SX CMT
Production: Size 5.5 feet: 3409 150 SX CMT
Liner: Size feet:

\$110.83

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/07/2001 11:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 400# hulls.
Perfs 2928' - 3349'. PBTB 3390'.
Sand back to 2875' w/5 sxs cement on top.
Shoot pipe off at 2400'.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/07/2001 12:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Sanded back to 2862' w/5 sxs cement on top.
Shot pipe off at 2226'.
Pulled to 1375'.
Allied pumped 100 sxs 60/40 pozmix - 10% gel with 300# hulls.
Pulled 5 1/2" to 700'.
Allied pumped 125 sxs with 100# hulls - cement circulated.
PCOH.
Topped off with 25 sxs.

RECEIVED
09-13-2001
SEP 13 2001
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

110

Signed Richard Williams
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 9-13-01

INV. NO. 2002060459

SEP 12 2001

REPLACEMENT CARD

AMERICAN LARIAT, INC.

P. O. BOX 936

HAYS, KS 67601

CONTR PIONEER DRLG. CO.

GEOL _____

#1 "C" R. MILLER

CTY ROOKS

FIELD RIFFE

18-7-17W

2910' FNL &

990' FWL, SEC

+	+	+
+	+	+
+	+	+

ELV 1841 KB SPD 4/28/83 CARD ISSUED 7/7/83

1836 GL

API 15-163-22,020

IP P. 50 BOPD, NW

ARB 3345-3354

LOG	Tops	Depth/Datum
ANH	1254 + 587
TOP	2771- 930
HEEB	2980-1139
TOR	3002-1161
LKC	3023-1182
MARM SD	3255-1414
MARM LM	3292-1451
SIMP	3323-1482
ARB	3344-1503
PBTD	3398-1557
RTD	3410-1569

8 5/8 " 1274.84/500SX; 5 1/2 " 3410/125SX
 DST (1) 2793-2813 (TOP) / 30-60-60-90, REC 150' SW, SIP
 1047-1027#, FP 49-98#
 MICT - CO, PF (ARB) 3345-54 W/4 SPF, SWB DWN, GSO, NAT,
 SET 2 7/8 " TBG AT 3394, POP, P 50 BOPD, NW (GR 23°), 5/27/
 83

CORRECTION: 9/29/83 - WAS LKC 3250-1409
 NOTE: 4/28/83 - ORIGINALLY FIRST REPORTED IN NE NW SW

COPYRIGHT 1983
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

15-163-22,020
 18-7-17W
 2910' FNL &
 990' FWL, SEC