

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22018-00-00
Spot: CNESWNW Sec/Twnshp/Rge: 18-7S-17W
3630 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: MILLER Well Number: 3
County: ROOKS Total Vertical Depth: 3430 feet

Operator License No.: 7076
Operator Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 1294
Production: Size 5.5 feet: 3420
Liner: Size feet: 111.48

Well Type: OIL UIC Docket No: Date/Time to Plug: 9/11/00 4:00:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (316) 278-2476

Proposed Plugging Method: Ordered out 240 sxs 60/40 pozmix - 10% gel - 400# hulls.
Shot casing off at 2526'.
Prod Perfs at 3388' - 3390'.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/11/2000 5:45 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:
8 5/8" set at 1294' w/500 sxs. 5 1/2" set at 3420' w/130 sxs.
Sanded back to 3330' and topped w/5 sxs cement with a dump bailer.
Shot casing off at 2526'.
Pulled casing to 1670' - tied onto and pumped 110 sxs w/300# hulls.
Pulled casing to 970' - tied onto and spotted 40 sxs w/100# hulls.
Pulled casing to 570' - tied onto and circulated cement w/80 sxs.
Pulled casing out of the hole.
Hole standing full of cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 22 2000
09-22-2000
CONSERVATION DIVISION
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY.
Plugged through: CSG

District: 04

Signed Jay Pfeifer (TECHNICIAN)

INVOICED

DATE 9/22/00
WEL. NO. 2001060723

Form CP-2/3

SEP 19 2000