

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22164-00-00
Spot: CNWNESW Sec/Twnshp/Rge: 18-7S-17W
2310 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: MILLER Well Number: 4
County: ROOKS Total Vertical Depth: 3378 feet

Operator License No.: 7076
Operator Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

Conductor Pipe: Size feet:
Surface Casing: Size 8.62 feet: 1288
Production: Size 5.5 feet: 3375
Liner: Size feet: 109.79

Well Type: OIL UIC Docket No: Date/Time to Plug: 9/8/00 8:00:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (316) 278-2476

Proposed Plugging Method: Ordered out 240 sxs 60/40 pozmix - 10% gel - 500# hulls.
Prod.Perfs @ 2952'-2955'; 3148'-3153'; 3248'-3251'; 3281'-3287'.
Shot off casing at 2532'.

Plugging Proposal Received By: HUBERT DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/08/2000 10:00 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

8 5/8" set at 1288' w/450 sxs. 5 1/2" set at 3375' w/130 sxs.
Sanded back casing to 2900' and topped with 5 sxs cmt with a dump bailer. Shot casing off at 2532'.
Pulled casing to 1620' - tied onto and pumped 110 sxs w/300# hulls.
Pulled casing to 970' - tied onto and spotted 40 sxs w/200# hulls.
Pulled casing to 570' - tied onto and circulated cement w/75 sxs.
Pulled casing out of the hole.
Hole standing full of cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 22 2000
09-22-2000
CONSERVATION DIVISION
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

NO.

Signed Jay Pfeifer
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 9/22/00
INV. NO. 2001060723

SEP 19 2000