

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22012-00-00
Spot: SESWSWSW Sec/Twnshp/Rge: 18-7S-17W
315 feet from S Section Line, 371 feet from W Section Line
Lease/Unit Name: DIX (H-7) Well Number: 1
County: ROOKS Total Vertical Depth: 3279 feet

Operator License No.: 9126 Conductor Pipe: Size 13.375 feet: 89 **8106.57**
Op Name: STRIPPER OIL CO (RICHARD A. DREHER) Surface Casing: Size 8.625 feet: 1235 w/425 sxs cmt
Address: 410 S MADISON Production: Size 5.5 feet: 3278 w/150 sxs cmt
PLAINVILLE, KS 67663 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/13/2002 9:00 AM
Plug Co. License No.: 33007 Plug Co. Name: RGN COMPANY, INC.
Proposal Rcvd. from: RICK DREHER Company: STRIPPER OIL COMPANY Phone: (785) 434-7206

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 500# hulls.
CIBP at 3276'. Fluid level 600'.
Arbuckle Perfs 3273' - 3275'.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/13/2002 10:35 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 25 sxs 60/40 pozmix - 10% gel with 200# hulls,
followed with 22 sxs gel spacer, followed with 100 sxs 60/40 pozmix - 10% gel with 150# hulls.
Max. P.S.I. 1500#. S.I.P. 800#.
Hooked up to backside.
Allied pumped 75 sxs 60/40 pozmix - 10% gel with 50# hulls.
Max. P.S.I. 1000#. S.I.P. 500#.

RECEIVED
AUG 15 2002
08-15-2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Richard Williams

(TECHNICIAN)

INVOICED

DATE

8-19-02

INV. NO.

2003060241

Form CP-2/3

AUG 13 2002


A & M OIL, INC.
 1224 MAIN, BOX 271
 STOCKTON, KS 67669

#1 DIX (H-7)

18-7-17W
 315'FSL &
 371'FWL, SW/4

CONTR PIONEER DRILLING CO. CTY ROOKS

GEOL _____ FIELD RIFFF



ELV 1796 KB SPD 8/7/83 CARD ISSUED 2/16/84 IP P 50 BOPD, NW
1791 GL ARB OH 3278-3279
 API 15-163-22,012

SMP	Tops	Depth/Datum
ANH	1230+ 566
B/ANH	1263+ 533
TOP	2726- 930
HEEB	2934-1138
TOR	2956-1160
LANS	2977-1181
BKC	3203-1407
ARB	3272-1476
RTD	3279-1483

13 3/8 " COND AT 89/85 SX; 8 5/8 " 1234/425 SX; 5 1/2 " 3278/150 SX
 NO DST'S
 MICT - CO, (ARB OH), SWB DWN, GSO, NAT, SET 2 7/8 " TBG AT 3265, POP, P 50 BOPD, NW (GR 24°), 9/9/83

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

NOTE: CORRECTION 9/8/83 - ORIGINALLY FIRST REPORTED AS #1 CITY (H-7); 315'FSL&271'FWL, SW/4