

7-619-163-21899-00-00

12-11-82

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
SW SE SW, SEC. 18, T. 7 S, R. 17 W/Ex
feet from S section line
feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5900

Operator: Lawbanco Drilling Inc.
Name & Address: Box 289
Natoma, Ks.

Lease Name Lowry #9 Well # 1
County Rooks Rooks 3342 108.62
Well Total Depth feet
Conductor Pipe: Size 13 3/8 feet 110
Surface Casing: Size 8 5/8 feet 1230

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Lawbanco License Number 5900

Address Same

Company to plug at: Hour: 9:00 AM Day: 6 Month: July Year: 19 89

Plugging proposal received from Riya Musgrove

(company name) Lawbanco (phone)

were: Order 350 sks 65/35 poz 8% gel 400# hulls. 5 1/2" at 3341'. Perf
at 3301' - 16'.

RECEIVED
STATE CORPORATION COMMISSION
07-19-1989
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by D.F.B. (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: Day: 6 Month: 7 Year: 19 89

ACTUAL PLUGGING REPORT
Ran wireline to 3270'. Pumped down 8 5/8" 150 sks
cement w/150# hulls. 900# max 350# close. Pumped down 5 1/2" 100 sks cement w/
150# hulls. Max pres. 1800'. Closed 1000# pres. pumped down 8 5/8" 100 sks
cement w/100# hulls. Max pres. 900. Closed w/600#. Checked plug July 10, 1989.
Down 75'. Filled w/sand and 5 sks cement. Cut off pipe and capped and restored.

Remarks: Allied Cement

Remarks: (If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

DATE 7-21-89
INV. NO. 25382

E.D.S.

Signed Dale F. Baithazor (TECHNICIAN)