

8-26

4-060428

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-21,886-00-00

SE SW SE /4 SEC. 18, 07 S, 17 W
330 feet from S section line
1650 feet from E section line

Operator license# 6656

Lease M. Rogers well # 1

Operator: American Lariat

County Rooks

Address: 250 - 6th Avenue SW
Calgary Alberta, Canada
T2P3G6

Well total depth 3295 feet
Conductor Pipe: 13 3/8 inch @ 105 feet
Surface pipe 8 5/8 Inch @ 1232 feet

107.08

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Co Tools License# -

Address: _____

Company to plug at: Hour: 9:00A.M. Day: 26 Month: August Year: 93

Plugging proposal received from: Charlie Farr

Company: Consultant to American Lariat Phone: _____

Were: Order 250 sxs. 60s/40 posmix - 10% gel with flo-seal and hulls.
8 5/8" - 5 1/2" annulus squeezed 2-4-87 and witnessed by
Dennis Hamel.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 11:00A.M., Day: 26, Month: August, Year: 93

Actual plugging report: 13 3/8" to 110'. 8 5/8" to 1228'. 5 1/2" to
3322'. C.I.B.P. at 3268'. 13 3/8" - 8 5/8" annulus full of cement to
surface. Tied onto 8 5/8" - 5 1/2" annulus and pumped 15 sxs. cement.
Max. 500#. S.I.P. 500#. Tied onto 5 1/2" casing and pumped 25 sxs.
cement followed by 185 sxs. cement with 500# hulls. Max. 600#.
S.I.P. 300#.

RECEIVED
STATE CORPORATION COMMISSION
09-09-1993
SEP 09 1993

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES NO

Plugged through TUBING , CASING . Elevation: 1770 GL

I did observe the plugging. Herb Deines

(agent)
Form CP-2/3

INVOICED
DATE SEP 14 1993
INV. NO. 38634