

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22343-00-00
Spot: CNESESE Sec/Twnshp/Rge: 18-7S-17W
990 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: BROWN H A Well Number: 2
County: ROOKS Total Vertical Depth: 3365 feet

Operator License No.: 7076
Operator Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

Conductor Pipe: Size feet:
Surface Casing: Size 8.62 feet: 1220
Production: Size 5.5 feet: 3360
Liner: Size feet:

109.36

Well Type: OIL UIC Docket No: Date/Time to Plug: 9/6/00

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (316) 278-2476

Proposed Plugging Method: Ordered out 260 sxs 60/40 pozmix - 10% gel - 400# hulls.
Shot off casing at 2200'.
Prod Perfs @ 2723'-2727'; 2850'-2852'; 3043'-3046'; 3148'-3150'.

Plugging Proposal Received By: HUBERT DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 09/06/2000 3:00 PM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

8 5/8" set at 1220' w/425 sxs. 5 1/2" set at 3360' w/170 sxs.
Sanded back to 2675' & topped with 5 sxs cmt with a dump bailer.
Shot casing off at 2200'.
Pulled casing to 1550' - tied onto and pumped 110 sxs w/300# hulls.
Pulled casing to 900' - tied onto and spotted 40 sxs w/100# hulls.
Pulled casing to 500' - tied onto and circulated cement with 85 sxs.
Pulled casing out of the hole.
Hole standing full of cement.

RECEIVED
STATE CORPORATION COMMISSION
09 22-2000
SEP 22 2000

Remarks: ALLIED CEMENT COMPANY.

CONSERVATION DIVISION
Wichita, Kansas

Plugged through: CSG

District: 04

Signed

Jay Pfeifer

(TECHNICIAN)

INVOICED

DATE 9/22/00

INVOICE NO. 2001060723

Form CP-2/3

SEP 19 2000