

To: 6 041316 ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-2
API NUMBER 15-7-22-60 E-16831
NE SW SW, SEC. 11, T 7 S, R 17 WE

15-163-00798-60-01
TECHNICIAN'S PLUGGING REPORT

990 feet from S section line
4250 feet from E section line

Operator License # 30704

Lease Name Simons "B" Well # 1

Operator: Joe Amos

County Rooks 107.86

Name & Address

6445 S. Broadway

Well Total Depth 3319' feet

Wichita, Kansas 67203

Conductor Pipe: Size - feet -

Surface Casing: Size 8 5/8 feet 643' w/400 sx.

Abandoned Oil Well _____ Gas Well _____ Input Well SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Eng. & Allied Cementing License Number _____

Address Great Bend, Kansas and Russell, Kansas

Company to plug at: Hour: 8:00A.M. Day: 2 Month: August Year: 19 91

Plugging proposal received from Jim Rockhold

(company name) Rockhold Eng. (phone) _____

were: 5 1/2" casing set at 3131' w/175 sks. cement. Perfs. at 2915' to 3021'. Perf. anhy. at 1139'. Plug bottom with sand to 2850' w/5 sx. cement. Perf. at 832'. Perf @ 2416' and 2331' and 1516'. Ordered 250 sks. 65/35 poz. 8% gel. w/1/4 lb. flocele plus 500 sks. hulls. plus 100 sx. common.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:00P.M. Day: 2 Month: August Year: 19 91

ACTUAL PLUGGING REPORT Spotted 100 sx. common @ 832', followed w/100 sx. 60/40 poz.

8% gel. w/500 # hulls. Mixed in cement. Casing on vac. P.O.O.H. w/832' of 5 1/2"

casing. Hooked up to 8 5/8" S.P. Squeezed in 150 sx. cement w/200# hulls.

Max. 700#. S.I. 300#.

Remarks: Anhy. 1143 - Recovered 832' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

Did you observe this plugging.

INVOICED

DATE 10-4-91

INV. NO. 33243

J.L.S.

Signed Dennis L. Hamel (TECHNICIAN)