

6 031035

2-26-88
15-163-19156-00-01
API NUMBER 15- E-16831

126

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NE SW, SEC. 11, T 7 S, R 17 W/E

1650 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6484

Lease Name Simons Well # B-2 SWD

Operator: Thornton E. Anderson

County Rooks 105.30

Name & Address 212 N Marked St. 508
Wichita, Kansas 67202

Well Total Depth 3240 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1225

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated _____ (Elev. 1870 G. L.)

Plugging Contractor Allied (D-E-16,831) License Number _____

Address Russell, Ks.

Company to plug at: Hour: 10:00AM Day: 26 Month: Feb Year: 1988

Plugging proposal received from Carl Gilpin

(company name) Thornton Anderson (phone) _____

were: 8 5/8" at 1225' cwc. 4 1/2" at 3253' to 2500' TOC. Perf 2754' - 60' 64' - 70'.

Perfs 2995' - 3009' - 3030' - 3033'. Ordered 50 sks Common Cement and 300 sks ATL.

Allied Cement Co. K and R Water Truck.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 2:00 PM Day: 26 Month: Feb Year: 1988

ACTUAL PLUGGING REPORT Mix and pump 50 sks Common Cement through tubing from 1800'

circulated cement. Lay down tubing. Squeeze 4 1/2" w/115 sks ATL. Max 700. Close in

Psi 500#. 8 5/8" - 4 1/2" Annulus circulated 60 Bbl of fluid ahead of cement. Closed

in Annulus and squeezed down 4 1/2". Plug complete.

RECEIVED STATE CORPORATION COMMISSION

APR 22 1988

04-22-88

CONSERVATION DIVISION
Wichita, Kansas

Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED
is to be used to reserve this plugging.

DATE 4-25-88

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 20432

Carl Goodrow

FORM CP-2/3 LR
Rev. 01-84