

15-193-00007-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Thomas County, Sec. 22 Twp. 6S Rge. 35 (W)

Location as "NE/CNW/SW" or footage from lines C/SW SW NW

Lease Owner General Crude Oil Company

Lease Name F. M. Williams Well No. 1

Office Address 314 Commerce Building, Abilene, Texas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 24, 19 58

Application for plugging filed Verbal approval 9-22 19 58

Application for plugging approved Verbally approved 9-22 19 58

Plugging commenced September 24, 19 58

Plugging completed September 24, 19 58

Reason for abandonment of well or producing formation Well was nonproductive of oil or gas.

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes - Mr. A. D. Fabricius in Hill City, Kansas

Name of Conservation Agent who supervised plugging of this well Mr. A. D. Fabricius

Producing formation None Depth to top - Bottom - Total Depth of Well 5301 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand	Water	120	285	8-5/8"	381'	None
Dakota		1720	1760		None	-
Topeka		3945	4075		None	-
Heebner		4076	4108		None	-
Lansing		4108	4382		None	-
Marmaton		4388	4610		None	-
Arbuckle	Water	5002	5150		None	-
Reagan		5265	5301		None	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy drilling mud was pumped through the drill pipe from 5301 to 600 feet. While the open-ended drill pipe was suspended at 600 feet, a 20 sack cement plug was mixed and pumped by Sun Cementing Company through the drill pipe and then the drill pipe was pulled from the hole, leaving the cement plug from 540 to 600 feet. After the pipe was pulled from the hole, a wood plug was placed in the 8-5/8" surface pipe and pushed to 375 feet by re-running the open-ended drill pipe. Another 20 sacks of cement was mixed and pumped by Sun Cementing Company through the drill pipe. The drill pipe was then pulled from the hole and the cement plug was from 315 to 375 feet. Another wood plug was pushed to 40' and 10 sacks of cement was mixed and pumped by Sun Cementing Company through the drill pipe. This top plug extended from 0 to 40 feet. A steel plate was then welded over the surface pipe which was at the bottom of a cellar 6 feet deep.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Cementing Company

Address Hill City, Kansas

STATE OF Texas, COUNTY OF Taylor, ss.

F. A. Hunter (employee of owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. A. Hunter

314 Commerce Building, Abilene, Texas (Address)

SUBSCRIBED AND SWORN TO before me this 6th day of October, 19 58

Martha Wishert Notary Public.

My commission expires June 1, 1959

PLUGGING
FILE SEC 22 T. 6 R35W
BOOK PAGE 134 LINE 29

RECEIVED
STATE CORPORATION COMMISSION
10-8-58