

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-03125-00-00  
Spot: SESENW Sec/Twnshp/Rge: 12-9S-17W  
2970 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: BAXA Well #: 5  
County: ROOKS Total Vertical Depth: 3420 feet

Operator License No.: 3833  
Op Name: SHAIDA, JOHN H.  
Address: 4126 NORTH SWEET BAY CIRCLE  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	4.5	1285	0	w/unknown sxs cmt
PROD	5.5	3418	0	w/unknown sxs cmt
SURF	8.625	152	0	w/100 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/07/2005 9:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: JOHN SHAIDA Company: SHAIDA, JOHN H. Phone: (316) 636-2525

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel with 1000# hulls.  
Anhy. 1270' - 1299'. Salt 1614' - 1748'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/07/2005 1:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2150'. Allied pumped 210 sxs 60/40 pozmix - 10% gel with 500# hulls - lost circulation.  
Pulled tubing to 1000' - pumped 30 sxs cement with 150# hulls - circulated cement.  
PTOH. Squeezed 5 1/2" casing with 60 sxs cement.  
Max. P.S.I. 500#. S.I.P. 300#.  
Hooked up to 8 5/8" - instant pressure 1000#.  
5 1/2" x 4 1/2" annulus full of cement.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

*Richard Williams*

(TECHNICIAN)

INVOICED

DATE

9-21-05

WT. NO

2006060472

RECEIVED

SEP 20 2005

KCC WICHITA

Form CP-2/3

SEP 13 2005

ALKAY OIL COMPANY

#5

BAXA

12-9-17W

23

SE SE NW

Contr.

ROOKS

County

E 1996

Comm. 4-26-50

Comp. 9-22-50

IP

7 BOPD & 95% WTR

PHY POT

Tops	Depth	Datum
ANH	1270	+ 726
HEEB	3087	- 1091
LANS	3118	- 1912
ARB	3118	- 1422
T.D.	3122	- 1426

Casing

8" 152 3 BOPH & WTR  
 5" 3418 ACID 2000  
 SWB 40 BO & 40 BWP

WESTHUSIN POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

INVOICED