

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-19007-00-01
Spot: E2E2SE Sec/Twnshp/Rge: 26-11S-21W
1320 feet from S Section Line, 330 feet from E Section Line
Lease Name: BAUGHER Well #: 2
County: TREGO Total Vertical Depth: 3910 feet

Operator License No.: 30553
Op Name: UNREIN OIL CO
Address: 300 W. 40TH STREET
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3645		
PROD	5.5	3896	0	150 SX CMT
SURF	8.625	215	0	150 SX CMT

08
\$127

Well Type: EOR UIC Docket No: E27321.1 Date/Time to Plug: 09/19/2005 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: GLENN UNREIN Company: UNREIN OIL COMPANY Phone: (785) 628-6231

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 10% gel - 800# hulls.
DV tool at 1751' w/400 sxs.
Low fluid level.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/19/2005 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Allied rigged to 5 1/2" casing - pumped 320 sxs 60/40 pozmix with 800# hulls mixed in.
Max. P.S.I. 500#. S.I.P. 300#.
Cut hole in 8 5/8" and welded on a 2" nipple - pumped 5 sxs 60/40 pozmix into backside.
Blew out of top of head. No pressure registered.

Perfs:

Top	Bot	Thru	Comments
3676	3680		
3655	3669		
3615	3620		

RECEIVED
KCC
SEP 23 2005

Remarks: ALLIED CEMENTING COMPANY-TICKET #21011.

WICHITA, KS

Plugged through: CSG

District: 04

Signed

[Signature]
(TECHNICIAN)

INVOICED
DATE 9-23-05
VV No 2006060500

Form CP-2/3

SEP 20 2005

GLICKMAN-HOUSTON

#2 BAUGHER

26-11-21W
E2 E2 SE

Contr. CO TOOLS

TREGO

County

E 2310 RB Comm.

Comp. 8/30/62

90 BOPD & 4% WTR,
IP LANS-3655-59

160 BOPD/ARB 3894-3910

LOGS Tops	Depth	Datum
ANHY	1723	+ 587
TOP	3328	-1018
HEEB	3538	-1228
B/OREAD	3548	-1238
TOR	3563	-1253
LANS	3577	-1267
B/KC	3796	-1486
ARB	3894	-1584
TD	3910	-1600

Casing
8" 215;
5" 3896;

WAS: SAME OPR, ARB PROD 4/20/62:
DST 3350-75/1 HR, 430' MDY SW, BHP 1145-1080#;
DST 3606-30/1 HR, 420' GIP, 885' CL GSY O, 30'
MDY GSY O, BHP 802-802#;
DST 3647-62/1 HR, 60' MDY O, 135' OCM, 60'
V HOCM, BHP 975-955#;
DST 3664-74/1 HR, 420' G, 185' HOCM, 180'
GSY O, 180' WCO, 160' OCM, 60' W, BHP 855-
840#;
DST 3892-3910/1 HR, 240' G, 60' MDY O, 1910'
O, BHP 1099-1099#; CO TD
3910; FU 3000' O/I HR, SWB
140 BO/4 HRS:
NEW INFO: CO: PERF 12/3655-59:
ACID 1000: SWB BK LD: FU 750'
OIL, NO WTR:

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

GLICKMAN-HOUSTON

#2 BAUGHER

26-11-21W
E2 E2 SE

Contr. GLICKMAN OIL CO

TREGO

County

E 2310 RB Comm.

Comp. 4-20-62

IP 160 BOPD/ARB 3894

3910

LOG Tops	Depth	Datum
ANH	1723	+587
TOP	3328	-1018
HEEB	3538	-1228
B/OREAD	3548	-1238
TOR	3563	-1253
LANS	3577	-1267
B/KC	3796	-1486
ARB	3894	-1584
TD	3910	-1600

Casing
8" 215
5" 3896

DST 3350-75/1 HR, 430' MDY SW, BHP 1145-
1080#
DST 3606-30/1 HR, 420' GIP, 885' CL GSY O,
30' MDY GSY O, BHP 802-802#
DST 3647-62/1 HR, 60' MDY O, 135' OCM, 60'
V H OCM, BHP 975-955#
DST 3664-74/1 HR, 420' G, 185' H OCM, 180'
GSY O, 180' WCO, 160' OCM, 60' W, BHP
855-840#
DST 3892-3910/1 HR, 240' G, 60' MDY O,
1910' O, BHP 1099-1099#
WALZ POOL

+	+	+
+	+	+
+	+	+

CO TD: FU 3000' O/I HR: SWB
140 BO/4 HRS

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

RECEIVED