

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22342-00-02
Spot: SENV Sec/Twnshp/Rge: 18-9S-23W
1980 feet from N Section Line, 1980 feet from W Section Line
Lease Name: ALBERTSON Well #: 2 WSW OWWO
County: GRAHAM Total Vertical Depth: 1800 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1403		
PROD	7	1799	0	w/300 sxs cmt
SURF	10.75	134	0	w/100 sxs cmt

#58⁵⁰

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 06/30/2005 1:30 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 700# hulls.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/30/2005 2:30 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

7" production casing set at 1799' w/300 sxs cement.
10 3/4" surface casing set at 134' w/100 sxs cement.
Rigged up cementers to 7" casing - squeezed 145 sxs cement with 700# hulls.
Max. P.S.I. 700#. S.I.P. 400#.
10 3/4" - pressured up to 600#. No cement pumped.

Perfs:

Top	Bot	Thru	Comments
1512	1516		
1498	1508		
1356	1366		
1290	1340		
1042	1052		
1020	1030		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

ND

Signed Dennis L. Hamel
(TECHNICIAN)

AUG 30 2005

INVOICED
DATE 9-21-05
INV. NO. 2006060460

RECEIVED
SEP 20 2005
KCC WICHITA

JOHN O. FARMER, INC.
RUSSELL, KS 67665

18-09 -23W
C SE NW

#2 ALBERTSON WATER SUPPLY OWWO

site: 5 S & 1-3/4 E OF PENOKEE, KS.

city: GRAHAM

API 15-065-22342

contr: UNKNOWN

field: ERNST NW

geol:

fr
date 04/26/89

spd
date 04/05/89

drig
comp 04/06/89

card
issued 04/26/89

last
revised 04/26/89

	A		

ELV: 2340 KB LOG
tops.....depth/datum
CHEY SD1356 +984
B/CHEY SD1366 +974
PBD1403 +937
RTD OLD1800 +540

IP status:

WSW, CRETCS 1356-1366 ,
OLD INFO: OPERATOR WAS JOHN O. FARMER, INC., 2
ALBERTSON WATER SUPPLY, 12/16/86 12/16/86 ,
12/18/86 SET 10-3/4" 134 / 100 SX, 7" 1799 / 300 SX,
WSW, NIPPE 1498-1516 OA, (CARD ISSUED 03/12/87)
CONTR: JOHN O. FARMER, INC.
NO CORES OR DSTS
MICT - CO, PF (CED HILLS) 1498-1508 & 1512-1516, W /
1 SPF, WSW (POTENTIAL NOT RPTD)
NEW INFO: FR 04/26/89 , REWORKED 04/05/89 DC
04/06/89 MICT - CO, SET CIBP AT 1403, PF (CHEY SD)
1356-1366, W / 4 SPF, SET 2-7/8" TBG AT 1085, WSW
4/10/89 (POTENTIAL NOT RPTD)

COPYRIGHT 1989
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

MAILED