

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22947-00-00
Spot: SWNWSWSW Sec/Twnshp/Rge: 15-15S-18W
970 feet from S Section Line, 280 feet from W Section Line
Lease Name: WETTA Well #: 1-24
County: ELLIS Total Vertical Depth: 3757 feet

Operator License No.: 8902
Op Name: MAYS, SAM W., JR.
Address: PHILTOWER BUILDING 427 S BOSTO
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3445		
PROD	4.5	3704	0	150 SX CMT
SURF	8.625	1197	0	450 SX CMT

#122¹⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/15/2005 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 227-3410

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/15/2005 2:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back casing 3300' - topped with 4 sxs cement using a dump bailer.
Cut casing loose at 2230'.
Pulled up to 1850' - mixed and pumped 90 sxs cement with 300# hulls.
Pulled up to 1200' - spotted 40 sxs cement with 100# hulls.
Pulled up to 600' - spotted 40 sxs cement with 100# hulls.
Pulled up to 200' - circulated cement with 15 sxs.
POOH. Hole full of cement.

RECEIVED
SEP 22 2005
KCC WICHITA

Perfs:

Top	Bot	Thru	Comments
3610	3614		
3578	3581		
3356	3360		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Jay Pfeifer
(TECHNICIAN)

INVOICED
DATE 9-22-05
INV. NO. 2006060488

Form CP-2/3

SEP 15 2005

GRANT OIL & ALTA INC
9150 W JEWELL, #106

15-15-18W
#1-24 WETTA 970' FSL&
280' FWL, SW/4

LAKEWOOD, CO 80226
CONTR ALDRIL EXPLOR.

CTY ELLIOTT
FIELD LEIKER

GEOLOGIST ROLAND STARBUCK

E 2051 KB CM 3/25/82 CARD ISSUED 9/9/82 IP P 26 BOPD, NW
API 15-051-22,947 CONG 3578-3614 OA

+	+	+
+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
HEEB		3283-1232	
LANS		3332-1281	
BKC		3558-1507	
CONG		3578-1527	
ARB		3638-1587	
RTD		3757-1706	

8-5/8" 1197/450sx, 4 1/2" 3704/150sx

DST (1) 3449-92 (KC) / 30-30-30-45, 10' SO SPKD M, W / SCUM
OIL ON TOP OF TOOL, SIP 42-40#, FP 35-35 / 35-35#, HP
1782-1761#

DST (2) 3624-40 / 30-30-30-45, 5'M, NS, SIP 31-31#, FP 21-21
/ 21-21#, HP 2099-2078#

DST (3) 3565-3623 (CONG W / STR PKR) / 30-30-60-90, 180'
HOCM (10%G, 30%O), 180' VHOCM (30%G, 15%O), (TOOL PLUG-
GING THROUGHOUT), SIP 1146-1154#, FP 450-511 / 484-461#,
HP 1930-1910#

MICT - CO, PF (CONG) 3610-14 W / 2 SPF, SWB 10 BOPH, NW,
NAT, POP, P 29 BOPD, NW, (GR 33%), PROD DECL, OFF PMP 5/
27/82, MICT - CO, PF (CONG) 3578-81 W / 4 SPF, SWB 6 BOPH,
NW, POP, P 50 BOPD INITIALLY, DECL & STAB AT 26 BOPD, NW,
8/31/82

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS