

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20132-00-00
Spot: NWSESE Sec/Twnshp/Rge: 12-5S-22W
990 feet from S Section Line, 990 feet from E Section Line
Lease Name: BITTEL Well #: 1
County: NORTON Total Vertical Depth: 3470 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 SOUTH ST. FRANCIS PO BOX 2757
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	2.375	3288	0	115 SX CMT
PROD	4.5	3467	0	125 SX CMT
SURF	8.625	251	0	200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/15/2005 11:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: GARY REH Company: GORE OIL COMPANY Phone: (316) 263-3535

Proposed Plugging Method: Ordered out 100 sxs Swift Multi-Density Cement.
10/27/2004 - 2 7/8" liner set at 3288'.
Acid Service cemented with 115 sxs Acon II - circulated 15 sxs to pit.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/15/2005 12:15 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Swab hole down to 3200'.
Swift pumped 60 sxs Swift Multi-Density Cement down tubing.
Max. P.S.I. 500#. S.I.P. 450#.
Hooked up to 8 5/8" annulus.
Swift Services pumped 25 sxs SMD.
Max. P.S.I. 550#. S.I.P. 500#.
4 1/2" x 2 7/8" annulus full of cement.

Perfs:

Top	Bot	Thru	Comments
3467	3470	OH	COMPLETION

RECEIVED
KCC
SEP 23 2005
WICHITA, KS

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 9-23-05
INV NO 2006060498

SEP 19 2005

R.P. NIXON OPERATIONS
207 W. 12TH

#1 BITTEL

12-5-22W
NW SE SE

HAYS, KS 67601

CONTR ABERCROMBIE DRILLING CTY NORTON

GEOL _____ FIELD DENSMORE

E 2048 KB CM 10/3/78 CARD ISSUED 2/17/79 IP P 16 BOPD & 30% W
REAG SD OH 3467-70

+	+	+
+	+	+
-	+	+

API 15-137-20,132

SMP	TOPS	DEPTH	DATUM
ANH		1642	+ 406
BANH		1672	+ 376
HEEB		3180	-1132
TOR		3207	-1159
LKC		3223	-1175
REAG AD		3465	-1417
RTD		3470	-1422

8-5/8" 251/200sx, 4 $\frac{1}{2}$ 3467/125sx

NO LOG

NO DST'S

MICT - CO (REAG SD OH) SWB 1-3/4 BFPH,

90% OIL ON/FU 1700' (300'w) SWB2 $\frac{1}{2}$

BFPH, 90% OIL, RT, POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS