

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-137-20199-00-00

Spot: SENENE

Sec/Twnshp/Rge: 13-5S-22W

4290 feet from S Section Line,

330 feet from E Section Line

Lease Name: BITTEL

Well #: 4

County: NORTON

Total Vertical Depth: 3541 feet

Operator License No.: 5552

Op Name: GORE OIL COMPANY

Address: 202 SOUTH ST. FRANCIS PO BOX 2757  
WICHITA, KS 67201

String Size Depth (ft) Pulled (ft) Comment

L1 2.375 3339 0 150 SX CMT

PROD 4.5 3537 0 100 SX CMT

SURF 8.625 219 0 200 SX CMT

#115 08

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/15/2005 2:00 PM

Plug Co. License No.: 32382

Plug Co. Name: SWIFT SERVICES, INC.

Proposal Rcvd. from: GARY REH

Company: GORE OIL COMPANY

Phone: (316) 263-3535

Proposed Plugging Method: Ordered out 100 sxs Swift Multi-Density Cement with 400# hulls.  
Ran 2 3/8" tubing liner. Haliburton cemented with 150 sxs Mid Con cwc.

Plugging Proposal Received By: RICHARD WILLIAMS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 09/15/2005 3:30 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Swabed down to 3300'.  
Swift Services pumped 35 sxs Swift Multi-Density Cement with 100# hulls.  
Max. P.S.I. 800#. S.I.P. 800#.  
Hooked up to 8 5/8" backside and pumped 35 sxs SMD.  
Max. P.S.I. 200#. S.I.P. 200#.  
4 1/2" x 2 3/8" annulus full of cement.

Top	Bot	Thru	Comments
3537	3541	OH	COMPLETION

RECEIVED  
KCC

SEP 23 2005

WICHITA, KS

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

*Richard Williams*

(TECHNICIAN)

INVOICED

DATE

9-23-05

INV NO

2006060498

Form CP-2/3

SEP 19 2005

