

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-23508-00-00  
Spot: NESESE Sec/Twnshp/Rge: 13-32S-4E  
1007 feet from S Section Line, 480 feet from E Section Line  
Lease Name: MATTISON Well #: 3  
County: COWLEY Total Vertical Depth: 3058 feet

Operator License No.: 30169  
Op Name: DOUBLE "D" OIL COMPANY, INC.  
Address: 2009 JEAN COURT  
WINFIELD, KS 67156

| String | Size  | Depth (ft) | Pulled (ft) | Comment    |
|--------|-------|------------|-------------|------------|
| PROD   | 4.5   | 3036       |             | 200 SX CMT |
| SURF   | 8.625 | 205        |             |            |

# 99 39

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/09/2005 10:00 AM  
Plug Co. License No.: 5495 Plug Co. Name: MCPHERSON, BILL DBA MCPHERSON DRILLING CO.  
Proposal Rcvd. from: DONALD BUTLER Company: DOUBLE "D" OIL COMPANY, INC. Phone: (620) 221-3570

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL  
Date/Time Plugging Completed: 08/09/2005 11:45 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Sanded back to 2930' and capped with 6 sacks of cement on top of sand. Shot off 4-1/2" casing at 998' and POOH. RIH with tubing at 270'. Pumped and circulated 75 sacks of 60/40 posmix with 4% gel to surface.

Elmores Cement ticket #06144

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 2984 | 2990 |      |          |

RECEIVED  
KCC DISTRICT #2  
SEP - 1 2005  
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed Duane R. Krueger  
(TECHNICIAN)

INVOICED  
DATE 9-22-05  
CUST. NO. 2006060491

RECEIVED  
SEP 21 2005  
KCC WICHITA