

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-00612-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 12-30S-37W
2345 feet from N Section Line, 2433 feet from E Section Line
Lease Name: HOEHN Well #: 1-12
County: GRANT Total Vertical Depth: 2705 feet

Operator License No.: 4824
Op Name: PIONEER NATURAL RESOURCES USA,
Address: 5205 N. O'CONNOR BLVD.
IRVING, TX 75039

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2295		WITH 2 SX CMT
L1		2705		PERFORATED LINER
PROD 7		2433	0	WITH 800 SX CMT
SURF	10.75	586	0	WITH 325 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/25/2005 8:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 2295' WITH 2 SX CMT. 20 SX CMT INSIDE 7" AT 1600'. 30 SX CMT AT 600'. 10 SX CMT AT 60' TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/25/2005 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG CIBP @ 2295' WITH 2 SX CMT. TAG CMT AT 2278'. 2ND PLUG PUMP 27 BBL MUD FROM 2278-1600'. PUMP 20 SX CMT AT 1600'. 3RD PLUG PUMP 34 BBL MUD TO 612'. PUMP 35 SX CMT AT 612'. 4TH PLUG PUMP 13 BBL MUD FROM 400' TO 60'. 5TH PLUG PUMP 10 SX CMT AT 60' TO 0'. PRESSURE TO 250#. DUG OUT BRADENHEAD. FOUND PLATE WELDED ON 10 3/4". CUT HOLE IN PLATE. FULL OF FLUID. BACKSIDE FULL OF CMT.


Perfs:

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

INVOICED
DATE 9-21-05
INV. NO. 2006060469

District: 01



Signed

Ken Jehlik

RECEIVED (N)

SEP 14 2005

KCC WICHITA

Form CR-25