

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-24034-00-00
Spot: N2S2SW Sec/Twnshp/Rge: 2-35S-5E
837 feet from S Section Line, 4031 feet from E Section Line
Lease Name: WARREN SONS Well #: 1
County: COWLEY Total Vertical Depth: 3140 feet

Operator License No.: 3954
Op Name: JAED PRODUCTION CO., INC.
Address: PO BOX 902
ARKANSAS CITY, KS 67005

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3138		100 SX CMT
SURF	8.625	202		85 SX CMT

#102⁰⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/09/2005 3:00 PM
Plug Co. License No.: 33592 Plug Co. Name: BROYLES, DARREN DBA D & S WELL SERVICE
Proposal Rcvd. from: DARREN BROYLES Company: BROYLES, DARREN DBA D & S W Phone: (620) 441-7223

Proposed
Plugging
Method:

Fill sand to 2600' with 5 sxs cement. Shoot off 2000' POH. RIH with tubing @ 300' circ cement to surf.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 08/09/2005 6:50 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

8/9/2005 -- Set CIBP at 2570' and dumped bailer with 2 sacks of cement. Shot casing at 875'.
POOH with 14 jts (575') of 5-1/2" casing. Swedged, established circulation, and pumped 130
sacks of 60/40 posmix with 4% gel to surface. POOH with 8 jts of 5-1/2" (300'). Topped plug
off.

8/10/2005 -- Tagged cement plug at 6' from surface.

Consolidated Oilwell Service #5177

Perfs:

Top	Bot	Thru	Comments
3088	3090		
2734	2740		

RECEIVED
KCC DISTRICT #2
SEP 16 2005
WICHITA, KS

Remarks:

Plugged through: CSG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

INVOICED
DATE 9-22-05
INV. NO. 2006060492

RECEIVED
SEP 21 2005
KCC WICHITA

Form CP-2/3