

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-20259-00-00

Spot: SESENE

Sec/Twnshp/Rge: 2-21S-7W

2970 feet from S Section Line,

330 feet from E Section Line

Lease Name: ODEN

Well #: 1

County: RICE

Total Vertical Depth: 3505 feet

Operator License No.: 32755

Op Name: MA & MC OIL & GAS LLC

Address: 602 S. CLARK
LYONS, KS 67554

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3485	1865	75 SX CMT
SURF	8.625	173		160 SX CMT

\$113⁹¹

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/08/2005 1:30 PM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: JOE MAES

Company: QUALITY WELL SERVICE, INC.

Phone: (620) 727-3410

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER

WitnessType: PARTIAL

Date/Time Plugging Completed: 09/08/2005 4:00 PM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded open hole to 3430' and put 5 sacks of cement on top. Cut off casing at 1865'. Pulled to 1050' and pumped 35 sacks of cement. Pulled casing to 600' and pumped 35 sacks of cement. Pulled casing to 225' and circulated cement to surface.

60/40 posmix with 4% gel
Copeland Cement #25826

Perfs:

Top	Bot	Thru	Comments
3485	3505		

**RECEIVED
KCC DISTRICT #2
SEP 13 2005
WICHITA, KS**

Remarks:

Plugged through: CSG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

INVOICED
DATE 9-26-05
INV. NO 2006060502

**RECEIVED
SEP 26 2005
KCC WICHITA**

Form CP-2/3