

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21491-00-00
Spot: E2NESENE Sec/Twnshp/Rge: 28-26S-10W
1550 feet from N Section Line, 150 feet from E Section Line
Lease Name: HANSEN TRUST Well #: 1
County: RENO Total Vertical Depth: 4420 feet

Operator License No.: 33650
Op Name: WEST BAY EXPLORATION CO., INC.
Address: 13685 S. WEST BAY SHORE #200
TRAVERSE CITY, MI 49684

String Size Depth (ft) Pulled (ft) Comment
SURF 8.625 317

#143⁶⁵

Well Type: ~~OG~~ Dry Hole ^{KCC} UIC Docket No: _____ Date/Time to Plug: 09/01/2005 5:00 AM
Plug Co. License No.: 99998 ⁹⁻²²⁻⁰⁵ Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: ROGER PEARSON ^{RBDms} Company: WEST BAY EXPLORATION CO., IN Phone: (405) 843-8773

Proposed Plugging Method: 35 sxs @ 1500'; 35 sxs @ 900'; 35 sxs @ 370'; 25 sxs @ 60'; 15 sxs in rathole and 10 sxs in mousehole.

Plugging Proposal Received By: GREG EVES WitnessType: NONE
Date/Time Plugging Completed: 09/01/2005 7:00 AM KCC Agent: GREG EVES

Actual Plugging Report:

Perfs:

Pumped 35 sacks of cement at 1500'. Pulled drill pipe to 900' and pumped 35 sacks of cement. Pulled drill pipe to 370' and pumped 35 sacks of cement. Pulled drill pipe to 60' and circulated 25 sacks of cement to surface. 15 sacks of cement in the rathole and 10 sacks of cement in the mousehole.

Acid Services #10917

155 sacks of 60/40 posmix with 4% gel

RECEIVED
KCC DISTRICT #2
SEP - 7 2005
WICHITA, KS

Remarks:

Plugged through: DP

District: 02

Signed Greg Eves

(TECHNICIAN)

INVOICED
DATE 9-22-05
INV. NO 2006060493

RECEIVED
SEP 21 2005
KCC WICHITA